

Detailed Estimate for Motorable of Road, damaged during Flood'2020

Block : Rahika

Division : Madhubani

Circle : Darbhanga

ABSTRACT OF COST

Name of Road : Jiwaachh Chowk se Kapileshwar


Length of Road : 4.00 Km


Extd. Length : 171 Mtr.


Sl. No.	Item of Works	Unit	Quantity	Rate	Amount (Rs.)
1.	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E.I.	CUM	254.638 173 250.00	1867.76	475,603.00 2,52,250.00
				Total Rs.	5,35,48.00
				Add GST @ 12%	57,057.60
				Add L.Cess @ 1%	475.58
	Add. surcharge Fee		254.638 250.84 m ² x Rs. 1063.00 x 10 %		2,665.00
				Grand Total Rs.	6,35,856.00

Say Rs. 6,35,900.00

5,64,799.00



Junior Engineer
Rahika.


Assistant Engineer
Rahika.


Executive Engineer
RWD Work Division,
Madhubani.

सहायक अभियंता, आठ काठ सिट, बाग अना 50307-6 (मिना (पुल))
का पत्रित: 04.08.20 (मिना दिनांक: 21.02.21) के द्वारा सहायक अभियंता
के आदेश पर।

— Five lac Sixty four thousand four hundred ninety
— nine only.


Superintending Engineer
RWD, Works Circle, Darbhanga
23/02/21

Detailed Estimate for Motorable of Road, damaged during
Flood'2020

Name of Road : Jiwachh Chowk se Kapileshwar

Length of Road : 4.000 KM


Estd. Length : 171 Mtr.


Block : Rahika


Division : Madhubani

Circle : Darbhanga

S.N.	ITEM OF WORKS	MEASUREMENT (L x B x H/D)	QUANTITY
1-	Providing and laying Brick Bats including -- do -- do -- E/L.		
	CH: 1.00 to 2.00 Km	1 x 9.40 x $\frac{1}{2}$ (2.00 + 1.50) x 0.40 =	6.58
		1 x 10.50 x 3.75 x $\frac{0.60 - 0.225 + 0.60 + 0.45}{3} =$	23.63 16.74
		1 x 10.00 x 3.00 x 0.50 =	15.00
		7 x 2.50 x 2.50 x 0.40 =	17.50
		1 x 18.00 x 3.00 x 0.50 =	27.00
		3 x 5.00 x 3.75 x 0.40 =	22.50
	CH: 2.00 to 3.00 Km	1 x 20.00 x 3.75 x 0.50 =	37.50
		1 x 30.00 x 3.75 x $\frac{0.225 + 0.70 + 0.50}{3} =$	28.74 53.438
		1 x 14.00 x 4.00 x 0.50 =	28.00
		6 x 4.50 x 3.75 x 0.30 =	30.38
		Total 286.84-m'	254.638


Junior Engineer
Rahika.


Assistant Engineer
Rahika.


Executive Engineer
RWD Work Division,
Madhubani.