



FLOOD DAMAGE REPAIR (FDR)
YEAR 2020-21

FOR T/A

DISTRICT :- **BEGUSARAI**
BLOCK :- **MANSURCHAK**

CONSTRUCTION COST	:-	Rs. 4.366 Lac
TOTAL COST	:-	Rs. 4.366 Lac

GTSNY YOJNA

NAME OF ROAD :- **FLOOD DAMAGE REPAIR OF**
GANPATAUL TO GAUSPUR SOHILWARA

TOTAL LENGTH	:	3.750 KM
LENGTH DAMAGE DUE TO FLOOD	:	0.139 KM.

SUBMITTED BY:
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, TEGHRA

Name of Road
:-

Flood Damage Repair of
Ganpataul to Gauspur
Sohilwara

Year 2020-21

District

:-




Begusarai

Block


:-

Mansurchak

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.) As Per Estimate
1	COST OF FDR	3,71,602.00
2	Add L.C. @1%	3,716.00
3	ADD GST @ 12%	44,592.00
	Add S.F. @ 10% on Material Rate	16,592.69
	Total Rs. :--	4,36,502.69
	Say Rs. :--	4,36,600.00
	 J.E. RWD Teghra	 A.E. RWD Teghra
		 E.E. RWD Teghra

Techni' Camy Approved for Rs 4,36,600 = at least
four Lacs, Thirty six thousand, Six Hundred only


15/11/21
संयोजक निदेशक
सार्वजनिक कार्य विभाग
प्रारंभिक कार्य, पटना-800 001

SDB L. NO	NCR D Ref.N	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
Construction of road embankment materials obtained from borrow pitsall complete job as per clouse 300.1,300.2 with lead upto 1000m										
Qty From Calculation		Cum						166.275	173.05	28,774.00
Sheets										
Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job.										
Qty From Calculation		Cum						121.45	1680.02	2,04,034.00
Sheets										
Supplying of empty cement bag (sythetic should be old but in good condition of 1.2 cafcapacing) with carriage,labour cost of roll nylon for streching of empty bag through local sand,laying,stacking properly.....all complete job as per specifications and direction of E/I.										
Qty From Calculation		Nos								
Sheets				190 X				25	4761.00	29.15
								Total	=	1,38,794.00
										371602.00
J.E		A.E.		E.E.						
RWD Teghra		RWD Teghra		RWD Teghra						

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंडौल-बखरी।

पत्रांक-...17-5446/मंडौल-बखरी, दिनांक-...11.12.21.../

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मंडौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।

प्रसंग : आपका पत्रांक-201709 दिनांक-...09.08.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।
अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन


कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल,
मंडौल-बखरी।

सामाजिक कार्य विभाग, कार्य प्रमण्डल, लेखडा द्वारा कराए गए पथों की जांच से संबंधित प्रतीवेदन

क्र.	पथ का नाम	क्षतिग्रस्त भाग (मी० में)	कराए गए कार्य	कराए गए निर्माण कार्य की राशि (रु० में)	GST @12%	L. Cess @1%	S. Fee @10%	Total	अवस्था
1	Flood Repair of Nurpur Bhagwati Asthan To Nurpur.	261	Sand Bag	416539.00	49985.00	4165.00	8045.00	478734.00	कार्य पूर्ण।
2	Flood Damage Repair of Road Chamtha REO Goptol To Cheriyatok.	10	Bricks Bats, Sand Bag	117758.00	14131.00	1178.00	7685.00	140752.00	कार्य पूर्ण।
3	Flood Damage Repair of Barauni PWD Road To Alapur Pasapur.	22	Sand Bag, E/W, Bricks Bats, GSB	122153.00	1222.00	14658.00	6827.00	144860.00	कार्य पूर्ण।
4	PMGSY Dasaratpur Road House of Ganga Gori To MMGSY Satbhaiya Tola.	20	E/w, Bricks Bats, GSB & Sand Bag.	53092.00	6371.00	531.00	1944.00	61938.00	कार्य पूर्ण।
5	Flood Damage Repair of Road NH Jhamatia Gat To Gopalpur.	163	Bricks Bats, Sand Bag, GSB	579759.00	69571.00	5798.00	21492.00	676620.00	कार्य पूर्ण।
6	Flood Damage Repair of REO Road Maranchikala To Harijan Tola Bhawanipur Ghat.	73	Bricks Bats, Sand Bag.	870266.00	104432.00	8703.00	28269.00	1011670.00	कार्य पूर्ण।
7	Flood Damage Repair of Basahi To Churamanchak.	252	Sand Bag, Brick bats	551214.00	66146.00	5512.00	17932.00	640804.00	कार्य पूर्ण।
8	Flood Repair of Patni Chowk RWD Road To Makratol.	181	Sand Bag.	235259.00	28231.00	2353.00	4544.00	270387.00	कार्य पूर्ण।
9	Flood Repair of X-Road Chan Barkhut Chamtha Ghat.	360	Sand Bag, E/w	310101.00	37212.00	3101.00	6015.00	356429.00	कार्य पूर्ण।
10	Flood Damage Repair of Kadramab (PWD Road) To (Dharampur) Bachhawara.	193	Sand Bag, GSB	183943.00	22073.00	1839.00	4545.00	212400.00	कार्य पूर्ण।
11	Flood Damage Repair of Ganpataul To Gauspur Sohilwara.	139	E/w, Bricks Bats, Sand Bag.	371602.00	44592.00	3716.00	16593.00	436503.00	कार्य पूर्ण।

उपरोक्त सभी पथों की जांच की गई जो संतोषप्रद है।


 Executive Engineer
 RWD (W) Div., Manjhaoul-Bakhari