



FLOOD DAMAGE REPAIR (FDR)

YEAR 2020-21

FOR T/A

DISTRICT
BLOCK

:- BEGUSARAI
:- BACHHAWARA

CONSTRUCTION COST

: Rs. 6.767 Lac

TOTAL COST

: Rs. 6.767 Lac

6T5NY Y0JNA

NAME OF ROAD : FLOOD DAMAGE REPAIR OF ROAD NH
JHAMATTIA GHAT TO GOPALPUR

TOTAL LENGTH

: 11.81 KM

LENGTH DAMAGE DUE TO FLOOD

: 0.163 KM.

SUBMITTED BY:

EXECUTIVE ENGINEER

R.W.D. WORKS DIVISION, TEQHNA

Flood Damage Repair of Road NH

Name of Road :- Jhamatia Ghat to Gopalpur
Year 2020-21

District :- Begusarai
Block :- Bachhauara

GENERAL ABSTRACT OF COST

No.	Item of Work	Amount (in Rs.) As Per Estimate
1	COST OF FDR	5,79,759.00
2	Add L.C. @ 1%	5,798.00
3	ADD GST @ 12%	69,571.00
	Add S.F. @ 10% on Material Rate	21,492.00
	Total Rs. :-	6,76,620.00
	Say Rs. :-	6,76,700.00
	J.E. 19.10.2020	
	RWD. Teghra	
	A.E. 19.11.20	
	RWD. Teghra	
	E.E. 19.10.2020	
	RWD. Teghra	

Tell him I am Approved Rs 6,76,700 = 60 km length
Survey by standard Survey standard only.

17.12.2021
19/12/21

SUB SL. NO	MOD D Ref.N	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1		Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/1 including cost of bricks,..... all complete job								
		Qty From Calculation Sheets	Cum					139.13	1590.02	2,33,733.00
2		Supplying of empty cement bag (sythetic should be old but in good condition of 1.2 catcapading) with carriage,labour cost of roll nylon for streching of empty bag through local sand,laying,stacking properly..... all complete job as per specifications and direction of E/1.								
		Qty From Calculation Sheets	Nos	439 619 X	25			10990.00	29.15	3,20,384.00
		Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.								
3		Qty From Calculation Sheets	Cum					14.31	1,791.92	25,642.00
								Total =		579759.00

JE
RWD Teghra

A.E.
RWD Teghra

E.E.
RWD Teghra

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंझौल-बखरी।

पत्रांक-...17.5440/मंझौल-बखरी,

दिनांक-...11/12/21...

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मंझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।

प्रसंग : आपका पत्रांक-201375 दिनांक-09.02.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।
अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन


11/12/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल,
मंझौल-बखरी।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा द्वारा कराए गए पथों की जाँच से संबंधित प्रतिवेदन

क्र० सं०	पथ का नाम	क्षतिग्रस्त भाग (मी० में)	कराए गए कार्य	कराए गए निर्माण कार्य की राशि (रु० में)	GST @12%	L. Cess @1%	S. Fee @10%	Total	अभियुक्ति
1	Flood Repair of Nurpur Bhagwati Asthan To Nurpur.	261	Sand Bag	416539.00	49985.00	4165.00	8045.00	478734.00	कार्य पूर्ण।
2	Flood Damage Repair of Road Chamtha REO Goptol To Cheriya Tok.	10	Bricks Bats, Sand Bag	117758.00	14131.00	1178.00	7685.00	140752.00	कार्य पूर्ण।
3	Flood Damage Repair of Barauni PWD Road To Alapur Pasopur.	22	Sand Bag, E/W, Bricks Bats, GSB	122153.00	1222.00	14658.00	6827.00	144860.00	कार्य पूर्ण।
4	PMGSY Dasarapur Road House of Ganga Giri To MMGSY Satbhaiya Tola.	20	E/w, Bricks Bats, GSB & Sand Bag.	53092.00	6371.00	531.00	1944.00	61938.00	कार्य पूर्ण।
5	Flood Damage Repair of Road NH Jhamatia Gat To Gopalpur.	163	Bricks Bats, Sand Bag, GSB	579759.00	69571.00	5798.00	21492.00	676620.00	कार्य पूर्ण।
6	Flood Damage Repair of REO Road Maranchikala To Harijan Tola Bhawanipur Ghat.	73	Bricks Bats, Sand Bag.	870266.00	104432.00	8703.00	28269.00	1011670.00	कार्य पूर्ण।
7	Flood Damage Repair of Basahi To Churamanchak.	252	Sand Bag, Brick bats	551214.00	66146.00	5512.00	17932.00	640804.00	कार्य पूर्ण।
8	Flood Repair of Patni Chowk RWD Road To Makratol.	181	Sand Bag.	235259.00	28231.00	2353.00	4544.00	270387.00	कार्य पूर्ण।
9	Flood Repair of X-Road Chan Barkhut Chamtha Ghat.	360	Sand Bag, E/w	310101.00	37212.00	3101.00	6015.00	356429.00	कार्य पूर्ण।
10	Flood Damage Repair of Kadramab (PWD Road) To (Dharampur) Bachhawara.	193	Sand Bag, GSB	183943.00	22073.00	1839.00	4545.00	212400.00	कार्य पूर्ण।
11	Flood Damage Repair of Ganpataul To Gauspur Sohilwara.	139	E/w, Bricks Bats, Sand Bag.	371602.00	44592.00	3716.00	16593.00	436503.00	कार्य पूर्ण।

उपरोक्त सभी पथों की जांच की गई जो संतोषप्रद है।

Executive Engineer
RWD (W) Div., Manjhaoul-Bakhari