



बिहार सरकार

FLOOD DAMAGE REPAIR (FDR)

YEAR 2020-21

FOR T/A

DISTRICT :- **BEGUSARAI**
BLOCK :- **BACHHAWARA**

CONSTRUCTION COST	:-	Rs. 10.117 Lac
TOTAL COST	:-	Rs. 10.117 Lac

GTSNY YOJNA

NAME OF ROAD :- **FLOOD DAMAGE REPAIR OF REO ROAD
MARANCHIKALA TO HARIJAN TOLA
BHAWANIPUR GHAT**

TOTAL LENGTH	:	2.021 KM
LENGTH DAMAGE DUE TO FLOOD	:	0.073 KM.

SUBMITTED BY:
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, TEGHRA

Name of Road :-

maranchikala to harijan tola
bhawanipur ghat

District

Year 2020-21

Block

:-

Begusarai

:-

Bachhawara

GENERAL ABSTRACT OF COST

Item of Work

Amount (in Rs.)

As Per Estimate

COST OF FDR

Add L.C. @ 1%

ADD GST @ 12%

Add S.F. @ 10% on Material Rate

8,70,266.00

8,703.00

1,04,432.00

28,269.00

10,11,670.00

10,11,700.00

[Signature]
19/10/2020

J.E.

RWD Teghra

Total Rs. :--

Say Rs. :--

A.E.

RWD Teghra

E.E.

RWD Teghra

Techli Comy Approved for Rs 10,11,700 = 10 Lacs
Seven thousand Seven Hundred Only

[Signature]
17.2.2021

प्रमाणित अधिकारी

प्रमाणित कार्य विभाग

15/1/20

Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
-------------	------	-----	--------	-------	--------	----------	------	-----------------

Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job.

Qty From Calculation Sheets Cum 147.19 1680.02 2,47,281.00

Supplying of empty cement bag (sythetic should be old but in good condition of 1.2 cftcapacing) with carriage,labour cost of roll nylon for stretching of empty bag through local sand,laying,stacking property.....all complete job as per specifications and direction of E/I.

Nos

854 81 X

25

21370.00

29 15

6,22,985.00

870266.00

Gnd
19/10/20

J.E

RWD Teghra

A.E

RWD Teghra

E.E

RWD Teghra

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंझौल-बखरी।

पत्रांक-...17.548.../मंझौल-बखरी,

दिनांक-...11.12.21...

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मंझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।

प्रसंग : आपका पत्रांक-201378 दिनांक-09.02.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।
अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन

11/02/2021

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल,
मंझौल-बखरी।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा द्वारा कराए गए पथों की जाँच से संबंधित प्रतिवेदन

क्र.सं.	पथ का नाम	क्षतिग्रस्त भाग (मी० मे)	कराए गए कार्य	कराए गए निर्माण कार्य की राशि (रु० मे)	GST @12%	L. Cess @1%	S. Fee @10%	Total	अभियुक्ति
1	Flood Repair of Nurpur Bhagwati Asthan To Nurpur.	261	Sand Bag	416539.00	49985.00	4165.00	8045.00	478734.00	कार्य पूर्ण।
2	Flood Damage Repair of Road Chamtha REO Goptol To Cheriyaatok.	10	Bricks Bats, Sand Bag	117758.00	14131.00	1178.00	7685.00	140752.00	कार्य पूर्ण।
3	Flood Damage Repair of Barauni PWD Road To Alapur Pasapur.	22	Sand Bag, E/W, Bricks Bats, GSB	122153.00	1222.00	14658.00	6827.00	144860.00	कार्य पूर्ण।
4	PMGSY Dasarapur Road House of Ganga Giri To MMGSY Satbhaiya Tola.	20	E/w, Bricks Bats, GSB & Sand Bag.	53092.00	6371.00	531.00	1944.00	61938.00	कार्य पूर्ण।
5	Flood Damage Repair of Road NH Jhamatia Gat To Gopalpur.	163	Bricks Bats, Sand Bag, GSB	579759.00	69571.00	5798.00	21492.00	676620.00	कार्य पूर्ण।
6	Flood Damage Repair of REO Road Maranchikala To Harijan Tola Bhawanipur Ghat.	73	Bricks Bats, Sand Bag.	870266.00	104432.00	8703.00	28269.00	1011670.00	कार्य पूर्ण।
7	Flood Damage Repair of Basahi To Churamanchak.	252	Sand Bag, Brick bats	551214.00	66146.00	5512.00	17932.00	640804.00	कार्य पूर्ण।
8	Flood Repair of Patni Chowk RWD Road To Makratol.	181	Sand Bag.	235259.00	28231.00	2353.00	4544.00	270387.00	कार्य पूर्ण।
9	Flood Repair of X-Road Chan Barkhut Chamtha Ghat.	360	Sand Bag, E/w	310101.00	37212.00	3101.00	6015.00	356429.00	कार्य पूर्ण।
10	Flood Damage Repair of Kadramab (PWD Road) To (Dharampur) Bachhawara.	193	Sand Bag, GSB	183943.00	22073.00	1839.00	4545.00	212400.00	कार्य पूर्ण।
11	Flood Damage Repair of Ganpataul To Gauspur Sohilwara.	139	E/w, Bricks Bats, Sand Bag.	371602.00	44592.00	3716.00	16593.00	436503.00	कार्य पूर्ण।

उपरोक्त सभी पथों की जांच की गई जो संतोषप्रद है।

11/07/2021
Executive Engineer
RWD (W) Div., Manjhaoul-Bakhari