

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- Area

3.Name of Road:- palm nola in persangur CH 1.5 km

A. For Road

1.Damage Location/Chainage :- 1.5 km

2.Damage Length :- 163 m

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 163 m

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-


(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-


(iv.)Restored Length :

n/n



Signature of JE/AE/EE







Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- Bilasi Madan pur Kursailghat At ch- 1.5 KM

कार्य का नाम :- FDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 34204A
..... 49 में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है

जिसकी प्राक्कलित लागत 9919080/- है।


उक्त पथ का निर्माण FDR योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में 5 पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदो का दर वर्तमान अनुसूचित दर के अनुरूप है।



कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, अरुणिया।



सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, अरुणिया।



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, अरुणिया।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-

Palasi Madanpur Kursallghat At Ch- 1.5 km

DISTRICT :-

Araria

BLOCK :-

Araria

Sl. No.

DESCRIPTION

AMOUNT
(LAKHS)

1

Filling of local sand

1134232.08

2

Labour for cutting 62mm to 75mm dia bamboo

67770.00

3

Supplying of EC bag, of local sand

378645.22

4

Supply and Carriage of brick bats

6731064.68

5

Supply, laying and carriage of 1000 mm HPC

466234.60

SUB TOTAL COST =

8777946.57

ADD GST @12% =

1053353.59

Add Labour cess @ 1% =

87779.47

Add Contingency @ 1% =

0.00

TOTAL (RS.) =

9919080

J.E

A.E

E.E

S.E

T/A for Rs. 9919080 = N (Ninety Nine Lakh Nineteen thousand Eighty Only)

28/1/20

Bill of Quantity

NAME OF ROAD :-		Palasi Madanpur Kursailghat At Ch- 1.5 km			
DISTRICT :-		Araria			
BLOCK :-		Araria			
Sl. No.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	cum	1809.30	626.89	1134232.08
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	MTR	1350.00	50.20	67770.00
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	NO	9926.47	38.15	378645.22
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	cum	3138.00	2,145.02	6731064.68
5	Supplaying and carriage of hume plpe 1000 mm dia , all complete job.	RM	97.50	4,781.89	466234.60
			A) SUB TOTAL =		8777946.57
			TOTAL COST =		8777947

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:- EE RWD Area

2.Name of Block:- Area

3.Name of Road:- Palen Madapur | Cusanglu CH 3.0 | 4

A. For Road

1.Damage Location/Chainage :- 3.0 | 4

2.Damage Length :- 136 m

3.Nature of Damage :- breach

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- Local soil, 3 | 800

(ii.)Equipments/Tools being used in Restoration works:- Truck, JCB

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 136 m

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

N/A

Signature of JE/AE/EE

Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- Palasi Madanpur Kurshailghat St ch- 3.00 km

कार्य का नाम :- FDR


में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

प्रारम्भ प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 3459315
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है


जिसकी प्राक्कलित लागत 3459315 है।
उक्त पथ का निर्माण MR योनान्तर्गत हुआ है एवं योजना अनुरक्षण
प्रवधि में ... 3459315 ... पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।



क्षेत्रीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, अरुणिया।



सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, अरुणिया।



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, अरुणिया।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-

Palasi Madanpur Kursallghat At Ch- 3.000 km

DISTRICT :-

Araria

BLOCK :-

Araria

Sl. No.

DESCRIPTION

AMOUNT
(LAKHS)

1

Filling of local sand

946353.14

2

Supply and Carriage of brick bats

2114987.18

SUB TOTAL COST =

3061340.32

ADD GST @12% =

367360.84

Add Labour cess @ 1% =

30613.40

Add Contingency @ 1% =

0.00

TOTAL (RS.) =

3459315

J.E

A.E

E.E

S.E

P/A for Rs - 34,59,315/- (Rupees thirty four Lacs Fifty Nine thousand three hundred fifteen Only.)

Bill of Quantity

NAME OF ROAD -		Palani Madanpur Kurnailghat At Gh- 3.000 km			
DISTRICT -		Araria			
BLOCK -		Araria			
Sl No.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-Charge	Cum	1500.00	620.09	940353.14
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	Cum	986.00	2,145.02	2114987.18
			A) SUB TOTAL =		3061340.32
			TOTAL COST =		3061340

[Signature]
J.E

[Signature]
21/9/22
A.E

[Signature]
21/9/22
E.E