



बिहार सरकार

**FLOOD DAMAGE REPAIR (FDR)**  
**YEAR 2020-21**

**FOR T/A**

**DISTRICT** :- **BEGUSARAI**  
**BLOCK** :- **MANSURCHAK**

<b>CONSTRUCTION COST</b>	:-	Rs. 0.620 Lac
<b>TOTAL COST</b>	:-	Rs. 0.620 Lac

**GTSNY YOJNA**

**NAME OF ROAD :-** PMGSY DASARATPUR ROAD HOUSE OF  
GANGA GIRI TO MMGSY SATBHAIYA  
TOLA

<b>TOTAL LENGTH</b>	:	1.245 KM
<b>LENGTH DAMAGE DUE TO FLOOD</b>	:	0.020 KM.

**SUBMITTED BY:**  
**EXECUTIVE ENGINEER**  
**R.W.D. WORKS DIVISION, TEGHRA**

**PMGSY Dasaratpur Road House  
Of Ganga Giri To MMGSY  
Satbhaiya Tola**

**Name of Road :-**

**Year 2020-21**

**District :-**

**Begusarai**

**Block :-**

**Mansurchak**

**GENERAL ABSTRACT OF COST**

No.	Item of Work	Amount (in Rs.) As Per Estimate
	COST OF FDR	53,092.00
	Add L.C. @1%	531.00
	ADD GST @ 12%	6,371.00
	Add S.F. @ 10% on Material Rate	1,943.64
	<b>Total Rs. :--</b>	<b>61,937.64</b>
	<b>Say Rs. :--</b>	<b>62,000.00</b>

*G.N.*  
19/10/2020  
**J.E.**

**RWD Teghra**

*L*  
19/10/20  
**A.E.**

**RWD Teghra**

*Amber E*  
19.10.2020  
**E.E.**


**RWD Teghra**


*Technical Drawing Approved As Rs 62,000.00 Say two thousand only.*

*(Signature)*  
17.2.2021  
15/2/21  
सिद्धि चंद, प्रमुख

MOR D Ref.N	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
	Construction of road embankment materials obtained from borrow pits .....all complete job as per clouse 300.1,300.2 with lead upto 1000m								
	Qty From Calculation Sheets	Cum					82.5	173.05	14,277.00
	Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job.								
	Qty From Calculation Sheets	Cum					11.14	1680.02	18,711.00
	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401								
	Qty From Calculation Sheets	Cum					3.09	1,909.65	5,908.00
	Supplying of empty cement bag (sythetic should be old but in good condition of 1.2 cafcapacing) with carriage,labour cost of roll nylon for streching of empty bag through local sand,laying,stacking properly.....all complete job as per specifications and direction of E/I.								
	Qty From Calculation Sheets	NO	19.485 X		25		487.00	29.15	14,196.00

  
 J.E.  
 RWD Teghra

  
 A.E.  
 RWD Teghra

Total = 53092.00  
  
 E.E.  
 RWD Teghra

कार्यपालक अभियंता का कार्यालय  
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंझौल-बखरी।

पत्रांक-...17.5440/मंझौल-बखरी,

दिनांक-...11...21.21.../

प्रेषक,

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, मंझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।

प्रसंग : आपका पत्रांक-201375 दिनांक-09.02.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।

अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन

  
11/02/2021

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग, कार्य प्रमण्डल,  
मंझौल-बखरी।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघडा द्वारा कराए गए पथों की जांच से संबंधित प्रतिवेदन

क्र.सं	पथ का नाम	क्षतिग्रस्त भाग (मी० में)	कराए गए कार्य	कराए गए निर्माण कार्य की राशि (रु० में)	GST @12%	L. Cess @1%	S. Fee @10%	Total	संमति
1	Flood Repair of Nurpur Bhagwati Asthan To Nurpur.	261	Sand Bag	416539.00	49985.00	4165.00	8045.00	478734.00	कार्य पूर्ण।
2	Flood Damage Repair of Road Chamtha REO Goptol To Cheriyaok.	10	Bricks Bats, Sand Bag	117758.00	14131.00	1178.00	7685.00	140752.00	कार्य पूर्ण।
3	Flood Damage Repair of Barauni PWD Road To Alapur Pasopur.	22	Sand Bag, E/W, Bricks Bats, GSB	122153.00	1222.00	14658.00	6827.00	144860.00	कार्य पूर्ण।
4	PMGSY Dasarapur Road House of Ganga Giri To MMGSY Satbhaiya Tola.	20	E/w, Bricks Bats, GSB & Sand Bag.	53092.00	6371.00	531.00	1944.00	61938.00	कार्य पूर्ण।
5	Flood Damage Repair of Road NH Jhamatia Gat To Gopalpur.	163	Bricks Bats, Sand Bag, GSB	579759.00	69571.00	5798.00	21492.00	676620.00	कार्य पूर्ण।
6	Flood Damage Repair of REO Road Maranchikala To Harijan Tola Bhawanipur Ghat.	73	Bricks Bats, Sand Bag.	870266.00	104432.00	8703.00	28269.00	1011670.00	कार्य पूर्ण।
7	Flood Damage Repair of Basahi To Churamanchak.	252	Sand Bag, Brick bats	551214.00	66146.00	5512.00	17932.00	640804.00	कार्य पूर्ण।
8	Flood Repair of Patni Chowk RWD Road To Makratol.	181	Sand Bag.	235259.00	28231.00	2353.00	4544.00	270387.00	कार्य पूर्ण।
9	Flood Repair of X-Road Chan Barkhut Chamtha Ghat.	360	Sand Bag, E/w	310101.00	37212.00	3101.00	6015.00	356429.00	कार्य पूर्ण।
10	Flood Damage Repair of Kadramab (PWD Road) To (Dharampur) Bachhawara.	193	Sand Bag, GSB	183943.00	22073.00	1839.00	4545.00	212400.00	कार्य पूर्ण।
11	Flood Damage Repair of Ganpataul To Gauspur Sohilwara.	139	E/w, Bricks Bats, Sand Bag.	371602.00	44592.00	3716.00	16593.00	436503.00	कार्य पूर्ण।

उपरोक्त सभी पथों की जांच की गई जो संतोषप्रद है।

Executive Engineer  
RWD (W) Div., Manjhaoul-Bakhari