

Inspection Report for Flood Damage Work

Date:-

1. Name of PIUs:- Ex. Er. R.W.D. near Div - Amri
2. Name of Block:- Jekhal
3. Name of Road:- Bhansi to Badiuda

A. For Road

1. Damage Location/Chainage :- CH- 7000-7048
2. Damage Length :- 48.00 M
3. Nature of Damage :- (rust damaged. (Diversion)
4. Details of Restoration Works:-
(i.) Material being used in Restoration Works:- local sand & Brick bats.
(ii.) Equipments/Tools being used in Restoration works:- Tractor with Trolly
(iii.) Procedure taken up in Restoration works:- filled all cuts properly in damaged area
(iv.) Restored Length :- 140.00 M

B. For Bridge

1. Damage Location/Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works:-
(i.) Material being used in Restoration Works:-
(ii.) Equipments/Tools being used in Restoration works:-
(iii.) Procedure taken up in Restoration works:-
(iv.) Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)
ग्रामीण कार्य विभाग
स्वयं प्रपण्डित - जिला मंत्री-2

ABSTRACT


Name of Road : Bhansia to Badiuda

Length : 9.120 km

District : Araria

Block : Jokihat

Sl. No	Particulars		Total Cost (in Rs.)
1	Cost of Road Restoration work	:	658361
2	Add G.S.T. @ 12%	:	79003
3	Add Labour Cess @ 1%	:	6584
Total Cost		:	743948
Say,		:	7.44,000/-


J. E.


A. E.


E. E.

T/A for Rs. 7.44,000/- (Rupees Seven Lacs forty four thousand) only


12/07/24

ESTIMATE FOR ROAD RESTORATION WORK

Name of Road:

Bhansia to Badliada

Block

Jokihat

length 5.12 km

Sl. No.	SSR Item No.	Chainage in M.	Cutting in M.	Description	No	Length (M)	Width (M)	H/D (M)	Gry.	Unit	Rate (in Rs.)	Amount (in Rs.)
1	8.7.7			Providing and cutting 62 mm to 75 mm dia bamboo pile to size and making shoes and driving etc. all complete job as per specification and direction of E/I								
		7000	7048	48	river side	0	145		2.50	0.00	No	
									0.00	M	50.20	0
2	8.7.8			Providing, fitting & fixing 62mm to 75 mm dia bamboo runners in position at every vertical pile with 150 m long nails or 26 avg G.I. wire including cost of G.I. or nails all complete job as per specification and direction of E/I								
		7000	7048	48		0	3.00	48.00		0.00	No	
									0.00	M	28.53	0
3	(1)			Providing and Filling empty cement bags with local sand, stitching the bags and placing including supply of stuff etc. all complete job as per specification and direction of E/I								
					2	48.00	0.40	0.90	34.56			
					29.4	bag=1m3						
						1016.04	bag		1016	1 bag	36.15	36763
4	(2)			Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9								
		7000	7048	48	(1.5+3.95+1.5)/3+2.31	1	48	5.00	2.3	554.40		
					Deduction for H.P. 1000MM dia	2	1.51	0.785	5.00	11.85		
					0.785	1.23x1.23=1.51						
									542.55	cum	628.89	340117.00
5	(3)			Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light, barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I excluding carriage cost of bricks.								
		7000	7048	48		1	48	5.00	0.45	109.00		
									0.00			
									109.00	cum	2148.02	231662.00
6	(4)			Providing and laying of R.C.C. Hume pipe Np2 in 1000mm dia with all complete job as per specification and direction of E/I								
					2	2	2.5		10.00	M	4781.88	47819.00
											Total=	658361
									Add GST 12%			79003
									Labour cess 1%			6584
											Total=	743948
											SAY=	743948

J.E.
23/12/2020
RWD (N) SUB DIV JOKHAT

J.E.
23.12.2020
RWD (N) SUB DIV

E.E.
RWD ARARIA
87/ 7,44,000=0