

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- Araria

3.Name of Road:- H/O Subalal to Chaukura H/O Majhi

A. For Road

1.Damage Location/Chainage :- 1st Km

2.Damage Length :- 228 m

3.Nature of Damage :- Breached

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- Bamboo, Etc logs, earth, 4/500, 6/500

(ii.)Equipments/Tools being used in Restoration works:- Tracker, JCB

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 228 m

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

22/8

Signature of JE/AE/EE 21/9/20 21/9/20 21/9/20

Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- House of Sub-AM Acharya via Major House of Major
कार्य का नाम :- DDQ

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 34/12

..... में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है
जिसकी प्राक्कलित लागत 2191222 है।


उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अधी में 11.1। पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


11-9-20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।


21/9/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।


21/9/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	House of Subit Lal to Chowk Via House of Najir	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Embankment	250150.01
2	Labour for cutting 62mm to 75mm dia bamboo	41992.30
3	Supplying of EC bag, of local sand	24233.29
4	Supply and Carriage of brick bats	1888687.84
	SUB TOTAL COST =	2205063.44
	ADD GST @12% =	264607.61
	Add Labour cess @ 1% =	22050.63
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	2491722

J.E

A.E

E.E

S.E

P/A Br Rs- 24,91,722.00 (Rupees Twenty Four Lacs Ninety one thousand Seven Hundred twenty two Only.)


23/11/20

Bill of Quantity

E OF ROAD :-		House of Subit Lal to Chowk Via House of Najir		
RICT :-		Araria		
CK :-		Araria		
DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)	
Construction of embankment with approved materials obtained from excavation for road way in soil using manual means for carrying of cut earth to embankment site 1.5 mt and lead upto 50 m, graded and	1183.05	211.45	250150.01	
Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	836.50	50.20	41992.30	
Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	635.29	38.15	24233.29	
Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	880.50	2,145.02	1888687.84	
5 Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	0.00	4,781.89	0.00	
	A) SUB TOTAL =		2205063.44	
	TOTAL COST =		2205063	

J.E

A.E

E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

NAME OF ROAD :-		House of Subit Lal to Chowk Via House of Najir							
DISTRICT :-		Araria							
BLOCK :-		Araria							
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
Construction of Embankment with Material Obtained from Borrow Pits									
Construction of embankment with approved materials obtained from excavation for road way in soil using manual means for carrying of cut earth to embankment site 1.5 mt and lead upto 50 m, graded and compacted to meet requirement of table 300.1, 300.2 with lift up to									
1	1st km	cum	1	76.00	5.50	0.90	376.20		
		cum	1	26.00	5.50	0.90	128.70		
		cum	1	22.50	5.50	0.90	111.38		
		cum	1	26.50	5.50	0.90	131.18		
		cum	1	88.00	5.50	0.90	435.60		
		cum	total qty:-				1183.05	211.45	250150.0073

No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.								
	1st km		1	76.00	3.50		266.00		
			1	26.00	3.50		91.00		
			1	22.50	3.50		78.75		
			1	26.50	3.50		92.75		
			1	88.00	3.50		308.00		
		Mtr.	total qty:-				836.50	50.20	41,992.30
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.								
	1st km	cum	2	20.00	0.30	0.90	10.80		
		cum	2	15.00	0.30	1.00	9.00		
		cum	2	10.00	0.30	0.90	5.40		
		cum	2	10.00	0.30	0.90	5.40		
		cum	2	20.00	0.30	0.90	10.80		
	Total No of E C Bags(3.4cum=100Bags) =			21.60	/	0.034	635.29		
		Each	Say No of Bage :-				635	38.15	24233.294

