

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D Works Circle, Chapra

DVISION – R.W.D Works Division, Marhaura

Name of Work – Motorable of Road from Amnaur bheldi road ke najdik se Mamla Prasad ke ghar se Amnaur pul tak

Block -

Amnaur

Estimated Cost – Rs 352286.00

2020-21

ABSTRACT OF COST

प्रतिवेदन

कार्य का नाम :- *Motable Road from Ammanur to Keldi road ko*
शीर्ष :- *maydik se Motable Road ko Ghar Tak Se Ammanur Pul Tak.*
प्राक्कलित राशि :- FDR
प्राक्कलित राशि :- 352 286/-
प्रखण्ड का नाम :- अमनौर

जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल मढ़ौरा के दिशा-निर्देशन में कुल रु0 / ~~35286~~ 352286/- के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bats, Sand Bag, Humie-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।

4/12/20
S. S.

Def.
जा.प्र.
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मढ़ौरा।

Inspection Report for Flood damage work

Date:

1. Name of PIUs- E.E. R.W.D. (W) Mathura.

2. Name of Block/Road- Amnour - Matnoble of Road from Amnour
Bhaldi dal ke naydile so Hamirkeghor so Amnour Pitha

A. For Road

1. Damage Location/Chainage : - 20 M.

2. Damage Length : - 324 M.

3. Nature of Damage : Road cutting due Flood.

4. Details of Restoration :

i Material being used in Restoration

: Brickbat, Sand filling

ii Equipment/Tools being used in Restoration works:

: Tractor, Roller, J.C.B. etc.

iii Procedure taken up in Restoration works

: Dumping, levelling, R.C.

iv Restored Length

: 324 M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AD/EE
04/12/20

Signature of JE/AD/EE
04/12/20

Signature
04/12/20

Er. Akhilesh Kumar
(Name of Inspector)

E.E.


R.W.D. (W) Division

SONEPUR.

Name of Work – Motorable of Road from Amnaur bheldi road ke najdik se Mamla Prasad ke ghar se Amnaur pul tak


Block – Amnaur

Sl No.	Particulars	Amount(In Rs)
A	Cost of Restoration Work	Rs311757.00
B	Add 12% GST on (A)	Rs 37411.00
C	Add 1% L.Cess on (A)	Rs 3118.00
	Total Cost	Rs 352286.00


J.E

RWD

Amnaur


A.E

RWD


Amnaur


E.E

RWD

Marhaura

T/A for Rs 3.52,286.00 (Rupees Three lac fiftytwo thousand two hundred eighty six) only.


अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा

Detailed Estimate

Name of Work - Motorable of Road from Amnaur bheldi road ke najdik se Mamla Prasad ke ghar se Amnaur pul tak

Sl.No.	Item	S No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in road ditches all complete as per approved design, specification and direction	1	324	0.65	0.75	157.95			
		Total				157.95	Cum	1909.87	301664
2	Finishing and spreading local sand over brick bats as per drawing and technical specification Clause 303.5.9	1	324	0.65	0.1	21.06	0		
		Total				21.06	Cum	479.27	10093
								TOTAL	311757

J.E
RWD
Amnaur

A.E
RWD
Amnaur

E.E
RWD
Marhaura