



FLOOD DAMAGE REPAIR (FDR)

YEAR 2020-21

FOR T/A

DISTRICT :- **BEGUSARAI**
BLOCK :- **BHAGWANPUR**

CONSTRUCTION COST	:-	Rs. 4.788 Lac
TOTAL COST	:-	Rs. 4.788 Lac

GTSNY YOJNA

NAME OF ROAD :- **FLOOD REPAIR OF NURPUR BHAGWATI
ASTHAN TO NURPUR**



TOTAL LENGTH	:	0.505 KM
LENGTH DAMAGE DUE TO FLOOD	:	0.261 KM.

SUBMITTED BY:
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, TEGHRA


**Name Of Road:- Flood Repair of Nurpur Bhagwati Asthan
to Nurpur
Year 2020-21**

**District :- Begusarai
Block :- Bhagwanpur**

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.) As Per Estimate
1	COST OF FDR	4,16,539.00
2	Add L.C. @1%	4,165.00
3	ADD GST @ 12%	49,985.00
	Add S.F. @ 10% on Material Rate	8,045.00
	Total Rs. :--	4,78,734.00
	Say Rs. :--	4,78,800.00
	 J.E. RWD Teghra	 A.E. RWD Teghra
		 E.E. 19.10.2021 RWD Teghra

Technically Approved Rs 4,78,800.00 say four
Lakh seventy eight thousand Eight Hundred only


17.2.21
प्रमाणित किया
जाती है कि
यह सच, सही है
15/2/21

DB NO	MOR D Ref.N	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
-------	-------------	-------------	------	-----	--------	-------	--------	----------	------	-----------------

Supplying of empty cement bag (sythetic should be old but in good condition of 1.2 cafcapacing) with carriage,labour cost of roll nylon for streching of empty bag through local sand,laying,stacking properly.....all complete job as per specifications and direction of E/I.

Qty From Calculation Sheets	Nos	566.735 X	25.00	14,168.00	29.40	4,16,539.00
-----------------------------	-----	-----------	-------	-----------	-------	-------------

G.R. Teghra
J.E.
RWD Teghra

h 19.10.20
A.E.
RWD Teghra

h 19.10.20
E.E.
RWD Teghra

ABSTRACT OF QUANTITY (QUANTITY CALCULATION SHEET)

NO		NO	LENGTH	WIDTH	DEPTH		QUANTITY	
	Supplying of empty cement bag (synthetic should be old but in good condition of 1.2 ccf/capacking) with carriage/labour cost of roll system for stretching of empty bag through local sand, laying, stacking properly all complete job as per specifications and direction of E/I.							
	10m to 450m	1	21	0.500	2.000	-	28.500	
		1	5.5	0.500	2.000	-	5.500	
		1	11.5	0.500	1.500	-	16.500	
		1	11	0.750	3.500	-	28.875	
		1	5.4	0.500	2.500	-	7.500	
		1	4.5	0.500	3.100	-	8.575	
		1	8.8	0.750	4.500	-	28.800	
		1	14.8	0.500	3.500	-	23.800	
		2	4	0.500	3.100	-	14.800	
		1	12.8	0.500	2.500	-	16.000	
		1	3	0.500	3.000	-	4.500	
		1	12.5	0.500	2.500	-	15.625	
		3	30	0.500	3.500	-	63.000	
		1	4.5	4.500	3.100	-	62.775	
		1	25.5	0.500	2.000	-	25.500	
TOTAL QUANTITY			250.9			-	566.735	Cum

JE
19/10/2022

A.E.

EE
19.10.2022

कार्यपालक अभियंता का कार्यालय ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मझौल-बखरी।

पत्रांक-...।.7.5/मझौल-बखरी,

दिनांक-...।.11.2021

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।

प्रसंग : आपका पत्रांक-2013/28 दिनांक-...।.08.2021

महोदय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।

अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन

11/08/2021

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमण्डल,
मझौल-बखरी।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा द्वारा कराए गए पथों की जाँच से संबंधित प्रतिवेदन

क्र० स०	पथ का नाम	क्षतिग्रस्त भाग (मी० में)	कराए गए कार्य	कराए गए निर्माण कार्य की राशि (रु० में)	GST @12%	L. Cess @1%	S. Fee @10%	Total	अभियुक्ति
1	Flood Repair of Nurpur Bhagwati Asthan To Nurpur.	261	Sand Bag	416539.00	49985.00	4165.00	8045.00	478734.00	कार्य पूर्ण।
2	Flood Damage Repair of Road Chamtha REO Goptol To Cheriyaok.	10	Bricks Bats, Sand Bag	117758.00	14131.00	1178.00	7685.00	140752.00	कार्य पूर्ण।
3	Flood Damage Repair of Barauni PWD Road To Alapur Pasopur.	22	Sand Bag, E/W, Bricks Bats, GSB	122153.00	1222.00	14658.00	6827.00	144860.00	कार्य पूर्ण।
4	PMGSY Dasarapur Road House of Ganga Giri To MMGSY Satbhaiya Tola.	20	E/w, Bricks Bats, GSB & Sand Bag.	53092.00	6371.00	531.00	1944.00	61938.00	कार्य पूर्ण।
5	Flood Damage Repair of Road NH Jhamatia Gat To Gopalpur.	163	Bricks Bats, Sand Bag, GSB	579759.00	69571.00	5798.00	21492.00	676620.00	कार्य पूर्ण।
6	Flood Damage Repair of REO Road Maranchikala To Harijan Tola Bhawanipur Ghat.	73	Bricks Bats, Sand Bag.	870266.00	104432.00	8703.00	28269.00	1011670.00	कार्य पूर्ण।
7	Flood Damage Repair of Basahi To Churamanchak.	252	Sand Bag, Brick bats	551214.00	66146.00	5512.00	17932.00	640804.00	कार्य पूर्ण।
8	Flood Repair of Patni Chowk RWD Road To Makratol.	181	Sand Bag.	235259.00	28231.00	2353.00	4544.00	270387.00	कार्य पूर्ण।
9	Flood Repair of X-Road Chan Barkhut Chamtha Ghat.	360	Sand Bag, E/w	310101.00	37212.00	3101.00	6015.00	356429.00	कार्य पूर्ण।
10	Flood Damage Repair of Kadramab (PWD Road) To (Dharampur) Bachhawara.	193	Sand Bag, GSB	183943.00	22073.00	1839.00	4545.00	212400.00	कार्य पूर्ण।
11	Flood Damage Repair of Ganpataul To Gauspur Sohilwara.	139	E/w, Bricks Bats, Sand Bag.	371602.00	44592.00	3716.00	16593.00	436503.00	कार्य पूर्ण।

उपरोक्त सभी पथों की जांच की गई जो संतोषप्रद है।

11/02/2021
Executive Engineer
RWD (W) Div., Manjhaoul-Bakhari