

RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name Of Work : Bunyadi Mohan yadav to Baba Narayan
Nagar

BLOCK

Riga

FDR

Rs. 174215.00. 2020-21

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

कार्य का नाम :- बुनीयादी मेहनत बाद से बाबा नारायण नारायण पथ में

बाद से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

प्राक्कलित राशि:- 209909.00

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक..... दिनांक
के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।

संलग्न प्राक्कलन 2020 के जुलाई माह मेंसीतामती..... प्रखंड में आई भीषण
बाढ़/अतिवृष्टि से क्षतिग्रस्त.....सीतामती मेहनत बाद से बाबा नारायण नारायण पथ में
बाढ़ से क्षतिग्रस्त 710/मीरममति मद से 45 यातायात चालू
करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs..209909.00..... हैं, उक्त
पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR
योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में हैं/नहीं हैं।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish भरकर MT
Sand Bag, बास बल्ला चचरी एवं लोकल बालू का प्रावधान किया गया है ताकि यातायात
चालू हो सकें।

प्राक्कलन के मदो का दर बर्तमान अनुसूचित दर से लिया गया है।

15/11/2020
कनीय अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रशाखा.....

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल.....।

15/11/21
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल सीतामढी।

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost


Name of Road : Bunyadi Mohan yadav to Baba Narayan Nagar
Length of Road : 0.0 KM
Block : Riga
DISTRICT : SITAMARHI

| S.No. | Particulars | Total Cost (in Lakh) |
|-------|--------------------------------|----------------------------------|
| 1 | Total Cost for Motorable Roads | ^{125768.0} 154173.00 |
| 2 | Labour cess @1% | ^{1258.0} 1541.73 |
| 3 | GST @12% | ^{22991.0} 18500.76 |
| | Total Cost of Road Repair | 174215.49 |
| | Say | 174215.00 |


Rs. 209909.00


JE


AE


EE

T/A is accorded for Rs. 209909.00 (Rupees two lakh nine thousand nine hundred nine only)


S.E.
R.W.D., Sitamarhi

EE published in
G.A. No. 244/10/21
dated 09/5/21 at 34/10/21

Schedule of Quantity

Name Of Work : Bunyadi Mohan yadav to Baba Narayan Nagar


Block Riga

| S.No | OF ITEMS | DESCRIPTION | QTY | UNIT | RATE | AMOUNT |
|------|----------|--|-------------------------|------|---------|----------------------------|
| 1 | | Sand Filling in Foundation Trenches as per Drawing & Technical Specification | 0.00 | Cum | 401.00 | 0.00 |
| 2 | | Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge. | 111.30 | | | 0.00 |
| | | Less 20% for Voids | -22.26 | | | |
| | | | 89.04 | Cum | 1546.00 | 137655.84 |
| 3 | | Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5 | 0.00 | m | 172.62 | 0.00 |
| 4 | | Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do - ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes) | 0.00 | no. | 23.12 | 0.00 |
| 5 | | Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe | 10.0 0.00 | m | 3158.69 | 31587.0 0.00 |
| 6 | | Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I. | | | | |
| | | Taking 20% of Brick Qty for Rabbish | 22.26 | Cum | 742.00 | 16516.83 |


Total 154172.67

Say 154173.00

185760.00


JE


AE


EE

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : Bunyadi Mohan yadav to Baba Narayan Nagar

| | L | W | H | VOLUME |
|---------------------------------|----------------|------|------|--------|
| | 3.00 | 2.00 | 0.50 | 3.00 |
| | 3.00 | 2.00 | 0.60 | 3.60 |
| | 6.00 | 3.00 | 0.50 | 9.00 |
| | 6.00 | 5.00 | 2.00 | 60.00 |
| | 3.00 | 1.00 | 0.50 | 1.50 |
| | 5.00 | 1.50 | 0.50 | 3.75 |
| | 16.00 | 1.50 | 0.60 | 14.40 |
| | 10.00 | 2.00 | 0.60 | 12.00 |
| | 3.00 | 2.50 | 0.50 | 3.75 |
| | 1.00 | 1.00 | 0.30 | 0.30 |
| | Total (in Cum) | | | 111.30 |
| Deduction of HP | | | (-) | 17.83 |
| | Total (in Cum) | | | 93.470 |
| LAYING HUME PIPE OF 1000 mm dia | | 4 | 2.5 | 10.000 |

15/1/2020

15/1/2020

10/1/21

22.1.21