

Inspection Report for Flood Damage Work

Date:

1. Name of PUs: E.E RIND Agha

2. Name of Block: Agha

3. Name of Road: Bazar Chowk to Dherangonj

A. For Road

1. Damage Location/Chainage :- 1st 8 meter

2. Damage Length :- 328M

3. Nature of Damage :- Breaks

4. Details of Restoration Works:- Bamboo, etc bags Lined bricks bats

(i.) Material being used in Restoration Works:- Tractor/JCB

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :- 328M

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

N/A

Signature of JE/AE/EE

Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- Baji Chowk to Dharamjay

कार्य का नाम :- PDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

सलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 342) 47
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है

जिसकी प्राक्कलित लागत 5202146 है।


उक्त पथ का निर्माण PDR योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में 1) पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।



कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।



सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	Bidi Chowk to Dharamganj Road	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	1963137.38
2	Labour for cutting 62mm to 75mm dia bamboo	54893.70
3	Supplying of EC bag, of local sand	147419.21
4	Supply and Carriage of brick bats	2366490.47
5	Supply, laying and carriage of 1000 mm HPC	71728.40
	SUB TOTAL COST =	4603669.16
	ADD GST @12% =	552440.30
	Add Labour cess @ 1% =	46036.69
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	5202146

[Signature]
21.9.20
J.E

[Signature]
21/9/20
A.E

[Signature]
21/09/20
E.E

S.E

T/A for Rs- 52,02,146.00 (Rupees fifty two lacs two thousand one hundred forty six only.)

[Signature]
28/11/20

Bill of Quantity

NAME OF ROAD :-		Bidl Chowk to Dharamganj Road	
DISTRICT :-		Araria	
BLOCK :-		Araria	
DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	3131.55	626.89	1963137.38
Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-charge.	1093.50	50.20	54893.70
3 Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	3864.71	38.15	147419.21
4 Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	1103.25	2,145.02	2366490.47
5 Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	15.00	4,781.89	71728.40
	A) SUB TOTAL =		4603669.16
	TOTAL COST =		4603669

[Signature]
21.9.20
J.E

[Signature]
21/9/20
A.E

[Signature]
21/9/20
E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

NAME OF ROAD :-		Bidi Chowk to Dharamganj Road							
DISTRICT :-		Araria							
BLOCK :-		Araria							
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge								
		cum	1	24.00	6.00	1.50	216.00		
		cum	1	11.00	6.00	2.20	145.20		
		cum	1	145.00	6.00	2.50	2175.00		
		cum	1	28.00	6.00	1.20	201.60		
		cum	1	35.00	7.50	1.50	393.75		
		cum		total qty :-				626.89	1963137.38

24.9.20

21/9/20

21/9/20

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.								
			1	24.00	4.50		108.00		
			1	11.00	4.50		49.50		
			1	145.00	4.50		652.50		
			1	28.00	4.50		126.00		
			1	35.00	4.50		157.50		
		Mtr.	total qty:-				1093.50	50.20	54,893.70
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.								
		cum	1	24.00	0.90	2.00	43.20		
		cum	1	11.00	0.90	1.50	14.85		
		cum	1	145.00	2.50	3.50	1268.75		
		cum	1	28.00	0.90	2.50	63.00		
		cum	1	35.00	0.90	2.80	88.20		
	Total No of E C Bags(3.4cum=100Bags) =		131.40 / 0.034				3864.71		
		Each	Say No of Bage :-				3865	38.15	147419.206

