



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

THAKURGANJ REO ROAD KE 19TH KM TO
BARCHAUNDI ROAD

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 2000		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD	2.000	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 3.586	Lacs	
ADD G.S.T @ 12%	Rs. 0.430	Lacs	
Add Seigniorage Fee @ 10 %	Rs. 0.245	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 4.261	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11-12-2020

1. Name of PIUs- E.E, R.W.D (W) Div. Kishanganj-2

2. Name of Block/Road- Thakurganj / Thakurganj road ke Bth KM to Barchundi road.

A. For Road

1. Damage Location/Chainage : 525M, 782M, 1152M, 1321M

2. Damage Length : 55.25M

3. Nature of Damage : crust damage

4. Details of Restoration :

i Material being used in Restoration

: Brick bats

ii Equipment/Tools being used in Restoration works:

: Trolley

iii Procedure taken up in Restoration works

:

iv Restored Length

: 55.25M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

N.A.

Signature of JE/AE/EE

11/12/2020
AE

BP
12/12

Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... Thakurganj REO Road RE 19 th km to
Barchaundi Road,
Head - FDR
Estimated cost - 04.281... Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Aringr.
11/12/20

J.E

R.W.D

Kishanganj-2

Aringr.
11/12/20

A.E

R.W.D

Kishanganj-2

Aringr.
11/12/20

E.E

R.W.D

Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : THAKURGANJ REO ROAD KE 19TH KM TO BARCHAUNDI ROAD
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 2.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	3.586
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		3.586
Add G.S.T. @ 12%		0.43
Add Seigniorage Fee @ 10 %		0.245
Total Cost of Restoration Work =		4.261

Amr
12/12/20
JE
RWD

Amr
11/12/20
AE
RWD

Amr
12/12/20
EE
RWD

Technically Approved for Rs. 4.261 Laes (four Lac twenty six thousand one hundred) only.

Amr
20/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज