

(6)

RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name Of Work : Gopinathpur Parmanendpur
to Yadav chamar tola

BLOCK

DUMRA

FDR

33,99,911=00
Rs. ~~34,81,835=00~~
~~33,00,911=00~~

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

कार्य का नाम :- जोपीनावापुर परमानन्दपुर से आइव - चमर पथ में
रोला

बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

प्राक्कलित राशि:- रु 3481835=00 33,99,911=00

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक..... दिनांक
के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।


संलग्न प्राक्कलन 2020 के जुलाई माह में इसरा प्रखंड में आई भीषण
बाढ़/अतिवृष्टि से क्षतिग्रस्त जोपीनावापुर परमानन्दपुर से आइव - चमर, रोला
पथ में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू
करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. 3481835=00 हैं, उक्त
पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR
योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में हैं/नहीं हैं।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish भरकर MT
Sand Bag, बास बल्ला चचरी एवं लोकल बालू का प्रावधान किया गया है ताकि यातायात
चालू हो सकें।

प्राक्कलन के मदों का दर बर्तमान अनुसूचित दर से लिया गया है।


04/01/21

कनीय अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रशाखा इसरा


04/01/2021

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल इसरा।

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल सीतामढ़ी।

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : Gopinathpur Parmanandpur to yadav
Length of Road : 0.0 KM chamber total
Block : DUMRA
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	30,08,655 = 00
2	Labour cess @1%	30097 = 00
3	GST @12%	361159 = 00
	Total Cost of Road Repair	3399911 = 00 3400911 = 00
	Say	3399911 = 00 34,00,911 = 00

eh
JE 09/01/21

AE
24/10/21

EE purbi for visit 24/10/21 EE
Gundamra R. 09/5/21 at 33,99,911 = 00

T/A is accorded for Rs. ~~34,00,911 = 00~~ (Rupees thirty
four lakh ^{nintynine thousand} ~~three~~ ^{one} nine hundred eleven only)

S.E.
10/5/21

S.E
RWD, Sitamarhi

Schedule of Quantity

Name Of Work : Gopinathpur Pannandpur Block DUMRA
to gadav charwar tota

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification	0.00	Cum	401.00	0.00
2	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	2172.72			0.00
	Less 20% for Voids	434.54			
		1738.18	Cum	1546.00	2687226=00
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4	Providing ,laying and placing empty cement bag filled with local sand including stitching with sutali etc. ----- do - ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 28% of Brick Qty for Rabbish	434.54	Cum	742.00	322429=00

Total 30,08,655=00


 4/11/2021
 JE


 12/11/2021
 AE

EE

MEASUREMENT

	L	W	H	VOLUME
	30.00	$(5.80+5.20)/2$	3.20	528.00
	30.00	$(6.10+5.40)/2$	$(3.20+2.80)/2$	500.25
	30.00	$(4.20+4.00)/2$	1.20	147.60
	5.00	3.95	0.90	17.77
	3*30.00	0.80	0.90	64.80
	2*20.00	$(5.80+4.20)/2$	2.90	580.00
	22.00	$(5.20+4.20)/2$	2.50 2.00	258.50 206.80
	10.00	$(5.00+4.10)/2$	1.20	54.60
	20.00	$(5.00+4.10)/2$	0.90	72.90
TOTAL QTY.:-				2224.42M³

2172.72 m³

eh
04/01/2021
M

eh
04/01/2021
MB