

RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name Of Work : Rewasi Panchayat Bhawan To Brahman

Toli Mahesiya

BLOCK

Riga

FDR

^{1265600.00}
Rs. ~~1397059.00~~

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

कार्य का नाम :- रेवासी पंचायत भवन के प्राथमिक टेली ग्रैजरीय..... पथ में

बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


प्राक्कलित राशि:- ~~1397059/-~~
1265600/-

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक..... दिनांक
के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।


संलग्न प्राक्कलन 2020 के जुलाई माह में रीवा..... प्रखंड में आई भीषण बाढ़/अतिवृष्टि से क्षतिग्रस्त रेवासी पंचायत भवन के प्राथमिक टेली ग्रैजरीय..... पथ में बाढ़ से क्षतिग्रस्त ग्रामीण मरम्मत F.D.R. मद से कर यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. ~~1397059/-~~ 1265600/- हैं, उक्त पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR-योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में हैं/त्रहीं हैं।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish ^{भरने} भरकर MT-Sand Bag, ~~बस बल्ला चबरी एवं लोकल बालू~~ का प्रावधान किया गया है ताकि यातायात चालू हो सकें।

प्राक्कलन के मदों का दर बर्तमान अनुसूचित दर से लिया गया है।


कनीय अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रशाखा.....


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल.....।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल सीतामढ़ी।


DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : Rewasi Panchayat Bhawan To Brahman Toli Mahesiya
Length of Road : 0.0 KM
Block : Riga
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	1119775.00 1236335.00
2	Labour cess @1%	1119775.00/100 12363.35
3	GST @12%	134597.40 148360.2
	Total Cost of Road Repair	1397058.55 1265510.00
	Say	1397059.00 Rs. 1265600.00



JE


AE


EE


T/A

T/A is accorded for Rs. 1265600.00 (Rupees twelve lakh sixty five thousand six hundred only)


S.E.
R.W.D., Sitamarhi

EE पुरपुरी का जॉय उद्घाटन - 244/10/2/21
सुचारु पंक्ति 30 09/5/21 का 340000

Schedule of Quantity

Name Of Work : Rewasi Panchayat Bhawan To Brahman Toli Mahesliya Block Riga

S.No	OF ITEMS	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1		Sand Filling in Foundation Trenches as per Drawing & Technical Specification	0.00	Cum	401.00	0.00
2		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	892.53			0.00
		Less 20% for Voids	161.71			
			714.03	Cum	1546.00	1103883.58
3		Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4		Providing ,laying and placing empty cement bag filled with local sand including stitching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5		Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6		Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
		Taking 20% of Brick Qty for Rabbish	161.71	Cum	742.00	119989.0
			178.51			132451.02

Total 1236334.59
Say 1236335.00

EE

JE

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : Rewasi Panchayat Bhawan To Brahman Toll Mahesiya

	L	W	H	VOLUME
	1.00	1.50	1.00	1.50
	1.00	1.50	1.00	1.50
	5.00	2.50	1.00	12.50
	7.00	$(4.50+4.00)/2$	0.50	14.87
	18.00	$(3.00+3.00)/2$	0.50	27.00
	20.00	3.00	0.45	27.00
	30.00	3.00	0.50	45.00
	30.00	3.00	0.50	45.00
	11.00	3.20	1.00	35.20
	10.00	2.50	0.80	20.00
	16.00	2.50	1.00	40.00
	3.50	1.80	1.50	9.45
	15.00	3.00	$(0.80+1.20)/2$	45.00
	5.00	2.90	0.80	11.60
	5.50	3.20	0.50	8.80
	3.50	3.00	0.30	3.15
	5.00	2.70	0.30	4.05
	10.00	$(2.50+2.30)/2$	1.00	24.00
	4.80	$(3.00+2.50)/2$	$(0.40+0.80)/2$	7.92
	12.00	$(3.50+3.00)/2$	1.00	39.00
	15.00	3.50	0.60	31.50
	4.00	3.80	2.50	38.00
	2.60	3.20	0.60	4.99
	16.00	$(3.00+3.50)/2$	$(1.00+2.50)/2$	91.00 175.00

					18.00	$(3.00+4.00)/2$	$(2.50+3.50)/2$ 172.25 (2.50+3.50)/2 = 129.4	189.00
					7.00	3.00	1.50	31.50
					Total (in Cum)			892.53 208.53

[Signature]
15/12/2020
AB

[Signature]
15/12/2020
AB

[Signature]
10/1/21

[Signature]
25-1-21