

Rate for motorability of road damaged by flood from Jagdish Singh House Gena Tol Chatbana to Brahman Tol Kalikapur for Year 2020

MR 3054

Length : 2.297 KM

Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E.I.	cum	As Per Appendix 1				719.78	1867.76	1342508.53
Laying Cement Concrete Pipe 600 mm dia NP3 (buried conduits) on first class	cum	As Per Appendix 2				5.00	2330.62	11653.10
								1342508.53
							Add 12% CST	161101.02
							Add 1% Labour Cess	151819.20
							Add 3% Ignorance Fee	12652.00
							TOTAL (in Rs.)	1593441.95
							Say (in Rs.)	1593441.95

Junior Engineer,

Rural Works Department,
Works Section, Kaluahi

Assistant Engineer,

Rural Works Department,
Works Sub Division, Kaluahi

Executive Engineer,

Rural Works Department,
Works Division, Madhubani

सहस्रमुखी नदी, जो बंगाल, बंगाल (यंग) 3000 (450) म -
- यंग नदी, जो बंगाल - 2.02 म - जो बंगाल - बंगाल -
- यंग नदी -
- Post-facto रा. रा. 1500, 900 - (Rural)
- Fifth class line. Limited Society. 1000 -

Superintending Engineer

RWD, Works Circle, Darbhanga

Name of Road:- Jagdish Singh House Gena Tol Chatbania to Brahman Tol Kalikapur ✓

Scheme :- MMGSY(SC)

Length : 2.297

Block : Kaluahi

Appendix - I

Measurement for restoration of Embankment & Shoulder with Brick Bat

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	400.00-500.00	4.00	1.50	0.60	0.30 (av.)	1.08
2	500.00-600.00	1.00	42.00	3.90	$\frac{0.45+0.60+0.55}{3}$ 0.60 (av.)	98.28 ✓
3	900.00-1000.00	1.00	24.00	3.00	0.55 (av.)	39.60
4		1.00	10.00	3.00	0.50 (av.)	15.00
5		1.00	38.00	3.20	$\frac{0.5+0.60+0.45}{3}$ 0.51666	72.96 ✓
6	1100.00-1200.00	1.00	49.00	3.20	$\frac{0.45+0.65+0.55}{3}$ 0.55	401.92 ✓
7		1.00	15.00	3.00	0.45 (av.)	20.25
8	1200.00-1300.00	1.00	26.00	2.00	0.40 (av.)	20.80
10		1.00	12.00	3.00	0.40 (av.)	14.40
11		1.00	37.00	2.80	0.60 (av.)	62.16
12	1300.00-1400.00	1.00	3.00	2.00	0.40 (av.)	2.40
13	1400.00-1500.00	1.00	2.00	2.50	0.45 (av.)	2.25
14		1.00	3.00	2.30	0.40 (av.)	2.76
15		1.00	8.50	2.00	0.45 (av.)	7.65
16		1.00	3.90	2.30	0.40 (av.)	3.59
17		1.00	12.20	2.50	0.60 (av.)	18.30
18	1500.00-1600.00	1.00	17.00	2.60	0.60 (av.)	26.52
19		1.00	2.70	2.00	0.55 (av.)	2.97
20		1.00	7.00	2.50	0.30 (av.)	5.25

62.82 ✓


- 86.2


Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
21	1700.00- 1800.00	1.00	2.20	2.10	0.35 (av.)	1.62
22		1.00	11.50	2.50	0.30 (av.)	8.63
23		1.00	7.00	2.20	0.35 (av.)	5.39
24		1.00	2.00	2.50	0.30 (av.)	1.50
25		1.00	1.25	1.50	0.40 (av.)	0.75
26		1.00	2.50	1.50	0.30 (av.)	1.13
27	1800.00- 1900.00	1.00	46.00	$(2.8+2.6)/2$	$(0.65+1.2+0.7)/3$	105.57
28		1.00	16.00	$(4+5.2)/2$	$(0.8+1.35+0.95)/3$	76.05
					TOTAL	248.78


Appendix - II

Laying Cement Concrete Pipe 600 mm dia NP3 (buried
conduits) on first class bedding of granular material including

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	1250.000	2.00	2.50			5.00
					TOTAL	5.00


8.1.21
Junior Engineer
Rural Works Department,
Works Section, Kaluahi


08.01.21
Assistant Engineer,
Rural Works Department,
Works Sub Division, Kaluahi


Executive Engineer
Rural Works Department,
Works Division, Madhubai