


### प्रतिवेदन


पथ का नाम :- Palace Road /w /Custard Street 2.5 Km


कार्य का नाम :- F.D.R

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संतन प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त .....  
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है  
जिसकी प्राक्कलित लागत ..... 40,77,367/- ..... है।  
उक्त पथ का निर्माण ..... 1.12 ..... योनान्तर्गत हुआ है एवं योजना अनुरक्षण  
अवधि में ..... पथ के कटे (क्षतिग्रस्त)  
भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद  
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट  
रूप से प्राक्कलन में दर्शाया गया है।  
प्राक्कलन मदो का दर वर्तमान अनुसूचित दर के अनुरूप है।

  
कनीय अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रशाखा, .....।

  
सहायक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अवर प्रमण्डल, .....।

  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, .....।

# SUMMARY OF COST ESTIMATE FOR THE PROJECT

| NAME OF ROAD :- | Palasi Madanpur Kursallghat At Ch- 2.5 km  |                |
|-----------------|--------------------------------------------|----------------|
| DISTRICT :-     | Araria                                     |                |
| BLOCK :-        | Araria                                     |                |
| Sl. No.         | DESCRIPTION                                | AMOUNT (LAKHS) |
| 1               | Filling of local sand                      | 417508.74      |
| 2               | Labour for cutting 62mm to 75mm dia bamboo | 22590.00       |
| 3               | Supplying of EC bag, of local sand         | 126215.07      |
| 4               | Supply and Carriage of brick bats          | 2934383.84     |
| 5               | Supply, laying and carriage of 1000 mm HPC | 107592.60      |
|                 | SUB TOTAL COST =                           | 3608290.25     |
|                 | ADD GST @12% =                             | 432994.83      |
|                 | Add Labour cess @ 1% =                     | 36082.90       |
|                 | Add Contingency @ 1% =                     | 0.00           |
|                 | TOTAL (RS.) =                              | 4077368        |

J.E

A.E


E.E


S.E


T/A for Rs - 40,77,368.00 (Rupees Forty Lacs Seventy Seven thousand Three Hundred Sixty Eight Only)

28/12/10

| Bill of Quantity |                                                                                                                                                                                     |                                           |                |            |              |
|------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|----------------|------------|--------------|
| NAME OF ROAD :-  |                                                                                                                                                                                     | Palasi Madanpur Kursailghat At Ch- 2.5 km |                |            |              |
| DISTRICT :-      |                                                                                                                                                                                     | Araria                                    |                |            |              |
| BLOCK :-         |                                                                                                                                                                                     | Arana                                     |                |            |              |
| SL No.           | DESCRIPTION OF ITEMS                                                                                                                                                                | UNIT                                      | QUANTITY       | RATE (Rs.) | AMOUNT (Rs.) |
| 1                | Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge                                          | cum                                       | 666.00         | 626.89     | 417508.74    |
| 2                | Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- In -charge. | Mtr                                       | 450.00         | 50.20      | 22590.00     |
| 3                | Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.                                                                | NO                                        | 3308.82        | 38.15      | 126215.07    |
| 4                | Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.                                                                     | cum                                       | 1368.00        | 2,145.02   | 2934383.84   |
| 5                | Supplaying and carriage of hume pipe 1000 mm dia , all complete job.                                                                                                                | RM                                        | 22.50          | 4,781.89   | 107592.60    |
|                  |                                                                                                                                                                                     |                                           | A) SUB TOTAL = |            | 3608290.25   |
|                  |                                                                                                                                                                                     |                                           | TOTAL COST =   |            | 3608290      |

  
J.E

  
A.E

  
E.E

# Inspection Report for Flood Damage Work

Date:- 21.09.2020

1.Name of PIUs:- E.C. P.W.D. Aravali

2.Name of Block:- Aravali

3.Name of Road:- 704 Aravali High road (Karni), Champ to palace puri road via Ranpur

## A. For Road

1.Damage Location/Chainage :- 131, 4th / 6th Km

2.Damage Length :- 369 M

3.Nature of Damage :- breached

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- B/B, E/C, bgs, bamboo, HP

(ii.)Equipments/Tools being used in Restoration works:- JCB & Tractor

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 369 M

## B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

N/A

Signature of JE/AE/EE

Signature


(Name of Inspector)

### प्रतिवेदन

पथ का नाम :- To, Arvic 115 paulkauri'claw & pccw'paw'paw vii Ram  
कार्य का नाम :- PDP  
में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त ..... 34.51.55 .....  
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है  
जिसकी प्राक्कलित लागत ..... 39.51.08 ..... है।  
उक्त पथ का निर्माण ..... 12.10.54 ..... योनान्तर्गत हुआ है एवं योजना अनुरक्षण  
अवधि में 12.10.54 ..... पथ के कटे (क्षतिग्रस्त)  
भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद  
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट  
रूप से प्राक्कलन में दर्शाया गया है।  
प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

  
कनीय अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रशाखा, 12.10.54

  
सहायक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अवर प्रमण्डल, 12.10.54

  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, 12.10.54

| SUMMARY OF COST ESTIMATE FOR THE PROJECT |                                                             |                |
|------------------------------------------|-------------------------------------------------------------|----------------|
| NAME OF ROAD :-                          | T04 Araria HQ Pachkauri Chowk to Palasi PWD Road Via Rampur |                |
| DISTRICT :-                              | Araria                                                      |                |
| BLOCK :-                                 | Araria                                                      |                |
| Sl. No.                                  | DESCRIPTION                                                 | AMOUNT (LAKHS) |
| 1                                        | Embankment                                                  | -591253.08     |
| 2                                        | Labour for cutting 62mm to 75mm dia bamboo                  | 96798.15       |
| 3                                        | Supplying of EC bag, of local sand                          | -989021.32     |
| 4                                        | Supply and Carriage of brick bats                           | -6679155.25    |
| 5                                        | Supply, laying and carriage of 1000 mm HPC                  | 71728.40       |
|                                          | SUB TOTAL COST =                                            | -8427966.20    |
|                                          | ADD GST @12% =                                              | -1011354.74    |
|                                          | Add Labour cess @ 1% =                                      | -84279.56      |
|                                          | Add Contingency @ 1% =                                      | 0.00           |
|                                          | TOTAL (RS.) =                                               | -9,523,590.51  |

374046.21

609139.19

2344825.80

3496537.74

419584.53

3496538

3951087.65

*Rep*  
21/7/20  
J.E

*at 62*  
21/7/20  
A.E

*21/7/20*  
E.E

S.E

T/A For Rs- 39,51,087.00 (Rupees-Thirty Nine Lacs Fifty One Thousand Eighty Seven Only.)

*21/7/20*

# Bill of Quantity

| NAME OF ROAD :- |                                                                                                                                                                                                                                                                            | T04 Araria HQ Pachkauri Chowk to Palasi PWD Road Via Rampur |            |                                     |
|-----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|------------|-------------------------------------|
| DISTRICT :-     |                                                                                                                                                                                                                                                                            | Araria                                                      |            |                                     |
| BLOCK :-        |                                                                                                                                                                                                                                                                            | Araria                                                      |            |                                     |
| Sl. No.         | DESCRIPTION OF ITEMS                                                                                                                                                                                                                                                       | QUANTITY                                                    | RATE (Rs.) | AMOUNT (Rs.)                        |
| 1               | Construction of embankment with approved materials obtained from excavation for road way in soil using manual means for carrying of cut earth to embankment site 1.5 mt and lead upto 50 m, graded and compacted to meet requirement of table 300.1, 300.2 with lift up to | <del>2790.25</del><br>1769                                  | 211.45     | <del>591253.08</del><br>374096.21   |
| 2               | Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-charge.                                                                                          | 1928.25                                                     | 50.20      | 96798.15                            |
| 3               | Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.                                                                                                                                                       | <del>25927.94</del><br>15963.04                             | 38.15      | <del>989021.32</del><br>609139.19   |
| 4               | Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.                                                                                                                                                            | <del>3413.80</del><br>1093.15                               | 2,145.02   | <del>6670455.25</del><br>2344825.80 |
| 5               | Supplying and carriage of hume pipe 1000 mm dia, all complete job.                                                                                                                                                                                                         | 15.00                                                       | 4,781.89   | 71728.40                            |
|                 |                                                                                                                                                                                                                                                                            | A) SUB TOTAL =                                              |            | <del>7836703.12</del> 3122491.53    |
|                 |                                                                                                                                                                                                                                                                            | TOTAL COST =                                                |            | <del>7836703</del> 3122492.00       |

*[Signature]*  
J.E

*[Signature]*  
A.E

*[Signature]*  
E.E