

Inspection Report for Flood Damage Work

Date:-

1. Name of PIUs:- Ex ER. R.W.D. Work Div. Araria

2. Name of Block:- Jakhia

3. Name of Road:- Singar Mahani to farmanpur

A. For Road

1. Damage Location/Chainage :- CH 2125 - 217

2. Damage Length :- 46.00 M

3. Nature of Damage :- Crust Damage

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:- Local sand and Brick bats

(ii.) Equipments/Tools being used in Restoration works:- Tractor with Trolley

(iii.) Procedure taken up in Restoration works:- filled all cuts properly in damage portion.

(iv.) Restored Length :- 46.00 M

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

कार्यपालिका-कियांता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल- किरानागंज-2

ABSTRACT


Name of Road : Singar mohani to parmanpur path


Length : 4.100 km


District : Araria

Block : Jokihat


Sl. No	Particulars		Total Cost (in Rs.)
1	Cost of Road Restoration work	:	1202627
2	Add G.S.T. @ 12%	:	144315
3	Add Labour Cess @ 1%	:	12026
Total Cost			: 1358968
Say,			: 13.59 13,59,000/-


23/12/2020
J. E.


23/12/2020
A. E.


E. E.

T/A for Rs-13,59,000/- (Rupees Thirteen Lac fifty Nine thousand) only


12/12/2020

ESTIMATE FOR ROAD RESTORATION WORK

Name of Road: Singar mohani to permanpur path

Block: Jokhat length: 4.10 km

Sl. No.	SSR Item No.	Chainage in M.	Cutting in M.	Description	No.	Length (M)	Width (M)	H/D (M)	Qty.	Unit	Rate (in Rs.)	Amount (in Rs.)
1	5.7.7			Providing and cutting 62 mm to 75 mm dia bamboo pile to size and making shoes and driving etc. all complete job as per specification and direction of E/I								
		2125	2171	46	0	230		5.00	0.00	No		
									0.00	M	50.20	0
2	5.7.8			Providing, fitting & fixing 62mm to 75 mm dia bamboo runners in position at every vertical piles with 150 m long nails or 38 swg G.I. wire including cost of G.I. or nails all complete job as per specification and direction of E/I								
		2125	2171	46	0	5.00	46.00		0.00	No		
									0.00	M	28.53	0
3				Providing and Filling empty cement bags with local sand, stitching the bags and placing including supply of suti etc. all complete job as per specification and direction of E/I								
					1	46.00	1.60	3.60	264.96			
					29.4	bag=1m3						
						7789.82	bag		7790	/ bags	38.15	297182
4				Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9								
		2125	2171	46		$(3.5+4.95+3.5)/3=3.98$						
				Deduction for H.P. 1000MM dia	0	0.79	1.23	7.90	0.00			
									1090.20	cum	626.89	683435.00
5				Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light, barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I excluding carriage cost of bricks.								
		2125	2171	46		$(0.45+0.60+0.45)/3=0.50$						
					1	46	4.5	0.50	103.60			
					0	0	0.0	0.00	0.00			
6				Providing and laying of R.C.C. Hume pipe Np3 in 1000mm dia with all complete job as per specification and direction of E/I					103.500	cum	2145.02	222010.00
					0	3	2.5		0.00	M	4781.89	0.00
											Total=	1202627
												144315
												12026
											Total=	1358968
											SAY=	1358968

RWD (W) SUB DIV JOKHAT

AE
RWD (W) SUB DIV

EE
RWD ARARIA