

Estimate for Motorable in Khajauli to maniyarwa sauth under FDR

Length:- 2.662KM

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Am
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix 1			301.709 406.09	1867.76	5,63
									Add GST 12%	6762
									Add L.Cess 1%	5635
									G. Total:-	3267

Junior Engineer
RWD(W) Section
Khajauli

Assistant Engineer
RWD(W) Sub Division
Khajauli

Executive Engineer
RWD(W) Division, Madhubani

सिमाना अंकित, आठ बाटो, दशैँ थाना-403M, 3(00017(सदर) का लागि :-
(300017) - दिनांक:-15/01/2021 के जेका अनुसार अर्थ अधिकारी के आदेश पर-

Post-Facto T/A PR. Rs. 6,68,845.00 (Rupees Six lakhs -
Sixty eight thousand eight hundred forty five only.)

Superintending Engineer
RWD, Works Circle, Darbhanga
22/01/2021

Name of road -Khajauli to maniyarwa sauth

Length -2.662km

pmgsy

chainage in (km)	no	length in (m)	width in (m)	depth in (m)	qty (cum)
0.020	1.00	19.10	3.50	0.65*0.45	43.45 30.08
0.020	1.00	19.10	3.50	0.65*0.45	43.45 30.08
	1.00	5.20	3.40	0.30	5.30
0.150	1.00	1.80	0.90	0.30	0.49
0.200	1.00	24.20	2.90	0.60*0.45	42.11 31.58
0.300	1.00	2.90	1.00	0.30	0.87
0.400	1.00	8.50	3.40	0.50*0.45	14.45 13.00
0.500	1.00	9.80	3.20	0.30	9.41
0.600	1.00	2.40	0.90	0.30	0.65
	1.00	5.00	3.00	0.85*0.45	12.75 6.75
0.700	1.00	1.00	0.90	0.30	0.27
	1.00	1.50	1.00	0.30	0.45
	1.00	9.10	0.90	0.90*0.55	7.37 4.50
	1.00	6.40	0.80	0.20	1.02
	1.00	8.70	1.20	0.15	1.57
	1.00	3.20	2.20	0.50*0.45	3.52 3.12
0.900	1.00	8.50	1.50	1.10	14.03
	1.00	11.70	0.90	0.30	3.16
	1.00	1.00	0.90	0.20	0.18
	1.00	1.00	0.70	0.20	0.14
1.500	1.00	16.00	3.10	0.45*0.30	22.32 14.88
1.700	1.00	27.20	2.20	0.90*0.45	53.86 26.93
2.000	1.00	1.00	1.00	0.15	0.15
	1.00	17.80	1.50	0.20	5.34
	1.00	19.60	2.00	0.45	17.64
2.200	1.00	5.00	3.20	0.30	4.80
	1.00	2.00	1.10	0.30	0.66
	1.00	15.70	2.00	0.40	12.56
2.300	1.00	13.30	3.00	0.45	17.96
2.600	1.00	11.50	3.10	0.40	14.26
	1.00	5.70	1.60	0.30	2.74
	1.00	7.00	2.50	0.30	5.25
	1.00	1.00	0.90	0.15	0.14
2.700	1.00	3.40	2.70	0.40	3.67
	2.00	0.90	0.75	0.15	0.20
	1.00	1.00	0.85	0.30	0.26
	1.00	10.80	0.90	0.30	2.92
	1.00	1.00	0.90	0.15	0.14
	1.00	3.40	1.10	0.45	1.68
	1.00	0.90	0.80	0.20	0.14
	1.00	4.10	1.40	0.30	1.72
3.000	1.00	7.30	1.20	0.60	5.26
	1.00	30.60	2.75	0.45*0.30	37.87 15.27
	1.00	9.00	7.00	0.45*0.30	28.35 18.90
	1.00	4.80	1.30	0.30	1.87
	1.00	2.20	1.20	1.20	3.17
				total	406.09-

1/12/20

AE

EE