

Estimate for Motorable in Mainapatti Bajrang Chowk to Kamla River Bandh
Via Dhanraj house

Length:- 2.306 KM

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix 1			195.89 267.36	1867.76	Rs 3,65,814.993
									Add GST 12%	43905.51
									Add L.Cess 1%	3659.49
									G. Total:-	5642
										2082

[Signature]
 1/10/20
 Junior Engineer
 RWD(W) Section
 Khajauli

[Signature]
 01/10/20
 Assistant Engineer
 RWD(W) Sub Division
 Khajauli

[Signature]
 28/10/20
 Executive Engineer
 RWD(W) Division, Madhubani

सहित अविना, 270 करोड़, धनराज चौक, धनुषा (450) के बीच:- 01/10/20
 दिनांक:- 15/01/2024 के द्वारा समीक्षा और 4A551 के अनुसार -
 Post-Facto T/A for Rs 4,34,262.00 (Rupees Four Lacs thirty four thousand two hundred and sixty two only).

[Signature]
 22/01/2024
 Superintending Engineer
 RWD, Works Circle, Darbhanga

Name of road:- Mainapatti Bajrang Chowk to Kamla River Bandh Via Dhanraj house

Length - 2.306 km							MR
s no	chainage	no	length	width	depth	qty	
	in (km)		in(m)	in (m)	in (m)	in (cum)	
1	1.200	1.00	10.50	$(0.9+2.2)/2$	1.50	24.41	20.34
2	to	1.00	23.50	$(2.2+3.2)/2$	1.55	98.35	79.32
3		1.00	12.10	$(1.5+2.9)/2$	0.90	23.96	13.31
4		1.00	11.30	$(2.5+2.8)/2$	1.20	35.93	22.45
6		1.00	29.50	$(3.7+4.5)/2$	0.70	84.67	60.47
					total	267.32	195.89

Ques
JE

AE

EE