


RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name of the Road :-
PARSURAMPUR TO DHANHARA
BLOCK : PARSAUNI

FDR

Rs. 262875.00

Year - 2019-20

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, BELSAND

प्रतिवेदन

पथ का नाम:-.....पथ

संलग्न प्राक्कलन 2020 के जुलाई माह में परखौली प्रखंड

में आई भीषण बाढ़ से क्षतिग्रस्त परशुरामपुर की धनधरा

.....पथ में बाढ़ से क्षतिग्रस्त मरमाति गद से यातायात चालू करने हेतु तैयार किया गया है।

जिसकी प्राक्कलित राशि Rs. 2.628 लाख (.....) है।

पथ के क्षतिग्रस्त भाग में आवश्यकता अनुसार Prick Bats, Rabbish भरकर यातायात चालू करने का प्रबंधन किया गया है।

प्राक्कलन बर्गमान अनुसूचित दर पर बनाया गया है।

Sagub

28.01.2021

मुख्य अभियंता
ग्रामीण कार्यविभाग, बेलसंड

Sreemath

28/01/21

सहायक अभियंता
ग्रामीण कार्यविभाग, बेलसंड

28.01.21

कार्यपालक अभियंता
ग्रामीण कार्यविभाग, बेलसंड

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : PARSHURAMPUR TO DHANHARA
Length of Road : 0.94km
Block : Parsauni
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Thousands)
1	Total Cost for Motorable Roads	232633.00
2	Labour cess @1%	2326.33
3	GST @12%	27915.96
	Total Cost of Road Repair	262875.29
	Say	262875.00

Sagunb

28.01.2021

JE

Sukumar

AE

28/1/21

EE

Technically approved for Rs 2.628 lac (Rs two lac sixty two thousand eight hundred) only

10/5/21

S.E

RWD Sitamarhi.

अनुमोदित और नगर पालिका
को 214 नम्बर दिनांक 17.02.2021
अनुमोदित 09.05.2021
अनुमोदित

Schedule of Quantity

PARSURAMPUR TO DHANHARA

Block Parsauni

S.No	OF ITEMS	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1		Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.				
		80% of Brick bat Qty.	134.35	Cum	1546.00	207710.12
3		Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4		Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5		Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6		Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
		Taking 20% of Brick Bats Qty	33.59	Cum	742.00	24922.53

Total **232632.65**

Say **232633.00**

Sagub
28/01/2021

JE

Skeema
28/01/21

AE

UA
28/01/21
EE

Details of Measurement of ditches filled by brick bats and rabbish

Sr. No.	DESCRIPTION	UNIT	NOS.	NOS.	LENGTH	BREATH	HEIGHT	QTY.	REMARKS
	Parsurampur to Dhanhara								
	1st Km	m ³		1	6.25	4.125	1.05	27.070	$B = (3.6 * 2 + 1.05) / 2$
		m ³		1	6.50	4.35	1.1	31.103	$B = (3.25 * 2 + 1.1 * 2) / 2$
		m ³		1	8.25	6.25	1.5	77.344	$B = (4.75 * 2 + 1.5 * 2) / 2$
		m ³		1	3.85	5	1	19.250	$B = (3.9 * 2 + 1.1 * 2) / 2$
		m ³		1	3.00	1.5	0.4	1.800	
		m ³		1	7.00	1	0.35	2.450	
		m ³		1	8.50	3.5	0.3	8.925	
	TOTAL	m ³						167.942	

Sagib
28.01/2021
J.E

Skumar
28/01/21
ME

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग
कार्य प्रमंडल, शिवहर

सं. 214 अमरपुर
शिवहर

दिनांक- 12/02/2021

उपस्थित-

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल शिवहर।

सूचना में,

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सीतामढ़ी।

विषय:- कार्य प्रमंडल बेलसंड के अधीन वर्ष 2020 की भयंकर बाढ़ से क्षतिग्रस्त पथों में
यातायात के पुनर्स्थापन हेतु तैयार किए गए प्राक्कलन की जांच के संबंध में।

संदर्भ:- भवदीय पत्रांक-900 दिनांक-12.09.2020

सूचना में,

उपरोक्त विषय में प्रासंगिक पत्र में दिए गए निर्देश के अनुपालन में कार्य प्रमंडल
बेलसंड के अधीन वर्ष 2020 की भयंकर बाढ़ से क्षतिग्रस्त पथों में यातायात पुनर्स्थापन हेतु
तैयार किए गए कार्यों का स्थल निरीक्षण किया गया। इस पत्र के साथ सलग्न सूची के 52 पथों पर
आवृत्ति जांचोपरान्त प्राक्कलन तकनीकी अनुमोदन हेतु समर्पित किया जा रहा है।

अनु-पथों की सूची (कुल 52 पथ) सलग्न।

विभागाध्यक्ष



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल शिवहर

ग्रामीण कार्य प्रमंडल बेलसंड के अन्तर्गत वर्ष-2020 के बाद से क्षतिग्रस्त
पथों के प्राक्कलन की सूची।

Sl No	Division	Block	Name of Road	Total cost in Lakh
1	Belsand	Parsouni	Ramani Middle School To Harpur Middle School Road	12.453
2	Belsand	Parsouni	Kanhaul Gajpatti To Bhulli REO Road	3.284
3	Belsand	Parsouni	Andhara PWD Road To Andhara Road Road	1.908
4	Belsand	Parsouni	Benipur To Dhurwar Road	12.267
5	Belsand	Parsouni	Belsand To Pamara Road	10.093
6	Belsand	Parsouni	Sundergrama Village To Vidhata Village At Manusara River	1.927
7	Belsand	Parsouni	Madanpur School West To Madanpur School East Road	5.313
8	Belsand	Parsouni	Muroul To Mushahari Tola Road	6.101
9	Belsand	Parsouni	Riga Road To Parsurampur Utter Tola	3.319
10	Belsand	Parsouni	Sarkhauli PWD To Kanhaul Gajpatti Road	8.679
11	Belsand	Parsouni	Pasurampur To Dhanhara Road	3.005
			TOTAL	68.349

[Signature]
12.2.20