

Estimate for Motorable in Mangrauni to khoir road under FDR

Length:- 5.350 KM

Item No.	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix (1)			160.20 m ³ 181.02	1867.76	338102. 2,99,215.00
								Add GST 12%	35,716.00 40572
								Add L.Cess 1%	2992.25 3381
								G. Total:-	17,02,712.00 382055

Q. No. 23/10/20
Junior Engineer
RWD(W) Section
Khajauli

28/12/2020
Assistant Engineer
RWD(W) Sub Division
Khajauli

28/12/2020
Executive Engineer
RWD(W) Division, Madhubani

खर्च अर्थात् 3,55,142.00 रु. का अनुमान 4 फरवरी, 2021 (454) रु.
4200 रु. 23/10/2020 दिनांक - 15/10/2020 से जारी किया गया है।
आवक 42 -

Post-Facto T/A 78 रु. 3,55,142.00 / रु. 4200
— Three lacs fifty five thousand one hundred and two

22/01/21
Superintending Engineer
RWD, Works Circle, Darbhanga

ngay road -Mangrauni to khoir road

Length -5.350km MR

s no	chainage	no	length	width	depth	qty
	in (km)		in(m)	in (m)	in (m)	in (cum)
1	0.000	1.00	4.30	1.00	0.60	2.58
2	to	1.00	7.00	2.00	1.00	14.00
3	0.100	1.00	19.30	2.00	1.25	48.25
4		1.00	14.00	1.00	1.50	21.00
5		1.00	7.00	1.30	1.25	11.375
6	0.200	1.00	7.00	2.00	1.50	21.00
7		1.00	30.00	3.50	0.30	31.50
8		1.00	10.00	3.50	0.30	10.50
					total	481.02

14.00 m³
48.25 m³
21.00 m³
11.375 m³
21.00 m³

120.20 m³

Gaig
21/12/20
JE

~~AE~~
28/12/2020

EE