

barahi tola laxmipur pmqsy under FDR

Length:- 2.972KM

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix 1			109.50 137.25 88.12 M ³	1867.76	2,04,528 256350 R. 1,64,588 24,542
									Add GST 12%	19,750.56 30762
									Add L.Cess 1%	204528 2045
									G. Total:-	2,31,107

Junior Engineer
RWD(W) Section
Rajnagar

Assistant Engineer
RWD(W) Sub Division
Rajnagar

Executive Engineer
RWD(W) Division, Madhubani

सहायक अभियंता रातो कालिग नम २७५-४०३८, द (०२१) (४६८)
का धातु :- ०३३५ (३०००) द (०२१) :- १५.०१.२०२१ डीटी एम. वि. वि. वि.
Post-ferro T/A १९५,३५० = ० (१९५,३५०)
— one lac ninety five thousand three hundred
— fifty only.

Superintending Engineer

RWD Works Circle, Darbhanga
22/01/2021

Name of road -House of siram misrapwd road to shrirampur barahi tola
laxmipur pmgsy

Length -2.972km mmgsy

s no	chainage in (km)	no	length in (m)	width in (m)	depth in (m)	qty in (cum)
1	0.100	1.00	5.50 4.50	2.50	0.30	4.13 3.37
2	0.120	1.00	6.50 3.50	2.00	0.30	4.88 2.1
3	0.130	1.00	2.50	2.00	0.50 0.25	2.50 1.125
4	0.200	1.00	2.50 2.00	1.50	0.30	1.13 1.35
5	0.300	1.00	2.50	2.50	0.30	1.88
6	0.35	1.00	4.50	1.50	0.30	2.03
7	0.4	2.00	4.50	1.20	0.30	3.24
8		3.00	1.50	1.10	0.20	0.99
9	0.490	4.00	2.10	1.20	0.20	2.02
10	0.500	1.00	5.70	2.50	0.20 0.30	4.28 3.207
11		1.00	7.50	2.10	0.30	4.73
12		1.00	2.10 1.5	2.20 1.5	0.30	1.39 0.67
13		3.00	2.50	2.30	0.30 0.15	5.18 2.58
14	0.700	1.00	3.50	2.00	0.30 0.20	2.10 1.4
15	0.800	1.00	3.00	2.50	0.30 0.20	2.25 1.5
16	0.850	6.00	2.50	1.50	0.20	4.50
17	0.900	1.00	3.50	0.85	0.20	0.60
18	1.000	1.00	6.50	3.50	1.20 1.80	40.95 28.43
19		1.00	6.50	1.20	0.30	2.34
20	1.020	1.00	✓ 1.50	3.50 2.00	0.30	1.58 0.9
21	1.100	1.00	2.00	1.50	0.30	0.90
22	1.200	4.00	1.50	1.20 1.50	0.30 0.20	2.60 1.8
23	1.300	1.00	2.50	1.50	0.30	1.13
24		1.00	3.50 3.00	2.50	0.30	2.63 2.25
25	1.950	1.00	12.50	1.50	1.20 0.30	22.50 5.62
26	2.000	1.00	7.50	0.90	0.30	2.03
27	2.200	2.00	1.50	1.20	0.30	1.08
28		1.00	15.00	2.00	0.30	9.00
29	2.420	1.00	6.50	0.90	0.30	1.76
					total	137.25

109.50 m

88.1213

JE
1/12/20

AE
28/12/20

EE