

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM HOUSE OF  
SAHWAZPUR TO MUSHAHARI

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

1767457.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- R. W. D. Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road House of Sahwa 2/4r to Muktarani

1. Damage Location/Chainage :

2. Damage Length : 315.0m

3. Nature of Damage : Flood Damage Ditch

4. Details of Restoration :

i Material being used in Restoration

: Local Sand, B/safe & Bamboo Pile

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Filling all cuts properly in damaged area.

iv Restored Length

: 315.0m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A

Signature of JE/ABEE

  
31/11/20  
A.S.

  
31/11/20  
EE

  
Signature

(Name of Inspector)

### Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2019 in ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM HOUSE OF SAHWAZPUR TO MUSHAHARI**

**Block:** FORBESGANJ


**District:** ARARIA

**Division :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	255.15	627.77	160175.91
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	2835.00	75.86	215059.14
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1890.00	40.06	75714.48
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	28997.15	37.35	1082948.31
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	23.63	1870.43	44188.97
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
<b>Total Amount (in Rs) =</b>					<b>1578086.82</b>

  
4/05/11/2020  
RWD WORKS  
DIV.  
FORBESGANJ

  
31/11/2020  
AE  
RWD WORKS DIV. FORBESGANJ

  
RWD WORKS  
DIV. FORBESGANJ



## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2019 in ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM HOUSE OF SAHWAZPUR TO MUSHAHARI**

**Block:** FORBESGANJ

**District:** ARARIA

**Divison :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	255.15	627.77	160175.91
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	2835.00	75.86	215059.14
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1890.00	40.06	75714.48
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	28997.15	37.35	1082948.31
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	23.63	1870.43	44188.97

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				1578087.00
	ADD 12.00 %GST=				189370.00
	SAY TOTAL AMOUNT =				1767457.00

*[Signature]*  
JE 28/11/2020

RWD WORKS  
DIV.  
FORBESGANJ

*[Signature]*  
31/11/2020

AE

RWD WORKS DIV. FORBESGANJ

*[Signature]*  
E.E.

RWD WORKS  
DIV. FORBESGANJ

Technically approved for (seventeen ~~lacs~~ lacs sixty seven thousand four hundred fifty seven Rupees Only)

*[Signature]*  
24/11/20  
**Superintending Engineer**  
Rural Works Department  
Bhadrakali