

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM MIRZAPUR TO  
HARIZAN TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

### ESTIMATED COST

~~5107915.00~~

4822082.00

Inspection Report for flood damage work

Date:

1.Name of PIUs-

2.Name of Block/Road-

**A.For Road**

1.Damage Location/Chainage :

2. Damage Lengh :

3.Nature of Damage :

4.Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

**B. For Bridge**

1.Damage Location/Chainage :

2. Damage Lengh :

3.Nature of Damage :

4.Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2019 in ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM MIRZAPUR TO HARIZAN TOLA**

**Block:** FORBESGANJ


**District:** ARARIA


**Division :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	2787.23	627.77	1749745.82
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	2988.00	75.86	226665.50
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	996.00	40.06	39900.33
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	51249.60	37.35	1914004.42
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				


		Cum	224.10	1851.91	415013.84
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	40.00	5382.71	215308.30
	TOTAL AMOUNT =				<del>43054.30</del> 4560638.00
	ADD 12.00 %GST=				<del>516632.00</del> 547277.00
	SAY TOTAL AMOUNT =				<del>5107915.00</del> 4822082.00

  
JE  
RWD WORKS  
DIV.  
FORBESGANJ

  
AE  
RWD WORKS DIV. FORBESGANJ

  
RWD WORKS  
DIV. FORBESGANJ

RS 4822082.00  
Technically approved for ~~(fifty one lacs seven thousand nine hundred fifteen Rupees only)~~ ~~Forty eight lacs twenty two thousand eighty two RS) only.~~

  
Superintending Engineer  
Rural Works Department  
Works Circle, Kishanganj