

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM MAJHUA TO
MANDAL TOLA

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

~~4433703.00~~

2440443.00

Inspection Report for flood damage work

Date:

1. Name of PIUs - E.C. R.M.D Forbesganj

2. Name of Block/Road - Forbesganj / majhwa to mandal Tola.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : $-(90m + 40m) = 130m$

3. Nature of Damage : Flood damage depth = 2m

4. Details of Restoration :

i Material being used in Restoration - L/gam, E.C. bag, runner, bamboo piling, S/bat. etc

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: - Filling all cuts properly in damage area
: - 130m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

} N.A

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM MAJHUA TO MANDAL TOLA

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj


Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.		1076.33		688243
			1827.33		833258
		Cum	2503.33	627.77	1571521.47
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.		1080 1440		8142924 10923820
		Mtr.	2340.00	75.86	177509.13
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.		380 480		1442224 1922920
		Mtr.	780.00	40.06	31247.25
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.		25681		11222624
			34241		127890424
		Each	43170.23	37.35	1612266.61
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				


		Cum	130.00	1870.43	243156.25
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.		60		
		meter	60.00	5382.71	322962.45
	TOTAL AMOUNT =		2178967-257	3222-20	3958663.00
	ADD 12.00 %GST=		261476-25	325387-20	475040.00
	SAY TOTAL AMOUNT =				4433703.00

322962-20
4433703

32558
3038807-00
2440443-20



E.E.


JE
RWD WORKS
DIV.
FORBESGANJ


AE
RWD WORKS DIV. FORBESGANJ

RWD WORKS
DIV. FORBESGANJ

2440443-20
Technically Approved for Rs. 4433703.00 (Rupees forty four
thousand four hundred and forty three
hundred and thirty three thousand seven hundred three only)


Superintending
Rural Works D
Works Circle.