



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Works Division-Marhaura

FDR

(2020-2021)

NAME OF WORK	Motorable of Road From <u>Panapur To</u> <u>Jipura via Ramdaspur Monda</u>		
DISTRICT	Saran		
BLOCK	Panapur		
LENGTH OF ROAD	4.800	KM	
ESTIMATED COST	4.517	Lac	

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs - E E Rwd (W) Division Marhaura

2. Name of Block/Road - Panapur

A. For Road

modorable to Road from Panapur to
sipara via Ramdas pur Monia

1. Damage Location/Chainage :

2. Damage Length : 83 M

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration works:

iii. Procedure taken up in Restoration works :

iv. Restored Length : 83 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration works:

iii. Procedure taken up in Restoration works :

iv. Restored Length :


C. Requirement of new CD/Bridge


i. Name of Road :

ii. Location/Chainage :

iii. Type of CD work/Length required :

- Upload one Photograph of damaged portion if available
- Attach minimum two photograph (during restoration & after restoration) photographs should be Geotags and at least one photo be captured in selfie mode.


8-12-2016
Signature of JE/AE/EE


Signature

(Name of Inspector)

प्रतिवेदन

कार्य का नाम :- पानापुर से जिपुरा भाया रामदसपुर मोरिया पथ ।

शीर्ष :- FDR

पथ की लं० :- 4.800 कि०मी०

प्राक्कलित राशि:- 4.517 लाख ।


प्रखण्ड का नाम:- पानापुर

जिला-सारण ।

प्रस्तुत प्राक्कलन शीर्ष MR-3054 Class-I अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा०का०वि०, कार्य प्रमंडल मढ़ौरा के दिशा-निर्देशन में कुल रु०- 4.517 लाख के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bats, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।


4.12.2020
B


04/12/2020
AE

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मढ़ौरा।

FDR

GENERAL ABSTRACT OF COST

Block:


Pamapur

District:- Saran

Length of Road:- 4.800 KM

Name of Road:- Pamapur to Jipura, via Ramdaspur Man'ya

SL. No.	Amount
A ESTIMATED COST :	4.517 lac.
TOTAL :	4.517 lac.


4.12.2020
Junior Engineer



04/12/2020
Asstt. Engineer

Executive Engineer

SE
RWD

T/A for Rs 4,51,700/- (four lakh fifty one thousand seven hundred only)


10.12.20
S.C.

Name of Road :-		Motorable of Road From Bhataga Half Ashan Se Bhataga Prathimk Vidhyalaya Hote Hare Sahdev Vishwakarma Dehagadh Vidhyalaya Tak		Block	Taralya
Sl. No.	Description	UNIT	QUANTITY	RATE	AMOUNT (in Rs.)
1	Providing Brick Bats Providing brick bats including spreading laying, Labour for dry graded jhama khoa folter under Brick Pitching or boulder pitching in slope or apron including light ramming etc. All complete job as per approved design specification and direction of E/I, including carriage cost of bricks.				
	Quantity As Per Annexure-1	CUM	209.75	2153.51	451699.41
				TOTAL COST =	451699.41
 4.12.2020 JE RWD  04/12/20 AE RWD EE RWD					

ANNEXTURE

Name of Road: - Panapur To Jipura via Ramdaspur
Moriga.

Block : - Panapur, L-4.800 km

No.	Description	Nos	Length (m)	Width (m)	Depth (m)	Unit	Quantity
1.	2400	1	20.00	1.00	1.00	cum	20.00
2.	2600	1	15.00	1.00	1.25	cum	18.75
3.	2700	1	30.00	1.50	1.00	cum	45.00
4.	2750	1	12.00	5.00	1.50	cum	90.00
5.	2750	2	6.00	2.00	1.50	cum	36.00

Total Qty: - 209.75 M³

JE
4.12.2020

A.E
04/12/20

E.E
R.W.D
Madhaur

Brick Bats Pitching Manual Means

SL.No.	DESCRIPTION	Unit	Quantity	Rate	Amount in Rs
6.6.1 WRD Bihar	Labour for dry graded jhama khoa folter under Brick Pitching or boulder pitching in slope or apron including light ramming etc. All complete as per approved design specification and direction of E/I.				
	Unit:-Per Cum				
	Taking Output =2.832 Cum				
	Unskilled Mazdoor	Nos.	3	287.00	861.00
	Add 6% Overhead Charge				51.66
	Rate for 2.832 Cum				912.66
	Rate Per Cum(Rs.)=				322.27
RCD	Cost of haulage Excluding Loading and Unloading				
	Haulage of Materials By Tractor Excluding Cost Of loading, unloading and stacking				
	Unit:-t.km				
	Taking output 3.60 tonnes load and lead 10 km =36.0 t.km				
	(i) Surface Road				
	Speed With load :15 km / hour.				
	a)Machinery.				
	Tractor 3.6 tonnes Capacity				
	Time Taken For onward haulage with load	hour	0.667	549.10	366.25
	Time Taken For empty return trip	hour	0.400	549.10	219.64
	b) Overhead Charges @0.06 on (a)				35.15
	Cost for 36 t.km=(a+b+c)/36				621.04
	Say RS.-				17.25
	(ii) Unsurface Gravel Road				
	Speed With load :12 km / hour.				
	Speed for empty return trip :20 km / hour.				
	a)Machinery.				
	Tractor 3.6 tonnes Capacity				
	Time Taken For onward haulage with load	hour	0.833	549.10	457.40
	Time Taken For empty return trip 0.50	hour	0.500	549.10	274.55
	b) Overhead Charges @0.06 on (a)				43.92
	Cost for 36 t.km=(a+b+c)/840.34				775.87
	Rate per t.km = (a+b+c)/3623.34				21.55
	Say RS.-				21.55

.1 RCD	Loading and Unloading of Stone Boulder / Stoneaggregate / sand / kanker / Moorum				
	Placing Tractor at loading point, loading with frontloader, dumping, turnig for return trip, excluding for haulage and return trip.				
	Unit = cum				
	Taking output = 2.25 cum				
	Time required for				
	i) Positioning of Tracter at loading Point		1 Min		
	ii) Loading by front end loader 1cum bucket @ capacity 25 cum per hour		5 Min		
	iii) Maneuvering, reverse, dumping and turnig for return		0 Min		
	iv) Wating time, unforeseen Contingencies etc.		0 Min		
	Total		6 Min		
	a) Labour				
	Mate				
	Mazdoor for loading and unloading	Day	0.03	305.00	9.15
	b) Machinery	Day	0.72	287.00	206.64
	Tractor 3.60 tonnes capacity	hour	0.10	549.10	54.91
	Front end loader 1 cum bucket capacity @ 25 cum/hour	hour	0.08	1403.00	116.45
	c) Overhead charges @ 0.06 on (a+b)				23.23
	Cost for 2.25 cum = a+b+c+d				410.38
	Cost for 2.25 cum = (a+b+c+d)/2.25				182.39
Note-	Unloading will be done manually.				
1	Suplying for Brick Bats (With OH)				
A	Basic Rate of Brick Bats		Per Cum	1017.00	1017.00
	Add overhead Charges 6%		0.06		61.02
	Total-				1078.02
	Surface Lead	km	7.00		
	Unsurface Lead	km	1.00		
	Factor(3.6/2.25)	cum	1.60		
B	Carriage (with OH)				
	(1.6 x 7 x 17.25) + (1.6 x 1 x 21.55) + 182.39				410.07
C	Cost of Labour for Pitching and Light Ramming as per WRD SOR 6.6.1 (with OH)				322.27
	Total (A+B+C)-				1810.36
	Add 1% Labour Cess (A+B+C)				18.10
	Add 12% GST(A+B+C)				217.24
	Add 10% cost of Material for seigniorage Fee		1.00	107.80	107.80
	Total Cost per Cum		Rs.-		2153.51