



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Govt. of Bihar



EMERGENT REPAIR OF ROAD FROM Ghataurapur (PMGSY Road) To Daudpur UNDER FDR



Name of the Road :-

EMERGENT REPAIR OF ROAD FROM Ghataurapur (PMGSY Road) To Daudpur UNDER FDR

DISTRICT	:	Patna	
DIVISION	:	BARH	
BLOCK	:	PANDARAK	
Total Length of Road	:		
Total Damaged Length Of Road	:		M
TOTAL COST OF CONSTRUCTION	:	4.647	Lacs
TOTAL COST OF PROJECT	:	4.647	Lacs

Executive Engineer
Rural Works Division,
BARH

प्रतिवेदन

कार्य का नाम : घटौरपुर (पी०एम०जी०एस०वाई०) पथ से दाउदपुर पथ का
आपातकालीन मरम्मत ।
क्षतिग्रस्त पथांश की लम्बाई:- 0.740 कि०मी०
प्राक्कलित राशि: मो० 4.647 लाख
मद : एफ० डी० आर०

प्रस्तुत प्राक्कलन, पंडारक प्रखण्ड अंतर्गत घटौरपुर (पी०एम०जी०एस०वाई०) पथ से दाउदपुर पथ का आपातकालीन मरम्मत कार्य का वर्तमान अनुसूचित दर पर मो० 4.647 लाख (चार लाख चौंसठ हजार सात सौ) रुपये मात्र का तैयार किया गया है । इस वर्ष की बाढ़ एवं अतिवृष्टि से पथ काफी क्षतिग्रस्त हो गया है । आवागमन अवरुद्ध है । विभागीय निर्देशानुसार पथ को यातायात योग्य बनाना है, तदनुसार पथ के क्षतिग्रस्त पथांश में जी०एस०बी०-1 भरकर पथ को यातायात योग्य बनाया गया है । यह पथ पी०एम०जी०एस०वाई० योजना के अंतर्गत NPLC द्वारा निर्मित है । कार्यहित एवं जनहित में इस प्राक्कलन की स्वीकृति अति आवश्यक है । इस पथ का सम्भरण नये मयूरसगरी में 30/8/2018 तारीख बनाया गया है जो विभाग को समर्थित है । इस स्वीकृति के पश्चात् विभाग के समस्त Restoration कार्य को Account for कर दिया जायेगा ।

BK
25/11/2020
कनीय अभियंता
पंडारक

Rb
25/11/20
सहायक अभियंता
पंडारक

25/11/20
कार्यपालक अभियंता
(ग्रामीण कार्य विभाग)
कार्य प्रमंडल, बाढ़

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

EMERGENT REPAIR OF ROAD FROM Ghataurapur
(PMGSY Road) To Daudpur UNDER FDR

DISTRICT

PATNA

BLOCK

PANDARAK

DIVISION

BARH

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	COST OF GSB GR- I	397921.82 397909.70
	TOTAL COST IN LACS =	3.979 3.979
	GST @ 12 % ON (PART A)	0.578 0.477
	LABOUR CESS GST @ 1 % ON (PART A)	0.040
	SUB TOTAL WITH GST & Labour cess	4.597 4.496
	CNC @ 1 %	0.040 0.045
	SEIGIINORANCE @10% of net	0.106
	TOTAL	4.643 4.647
	TOTAL COST OF PROJECT IN LACS =	4.643 4.647

B/S
25/11/2020
JE
RWD

R/S
25/11/20
AE
RWD

25/11/20
EE
RWD

Technically approved for Rs. 4.643 (Rupees four lakhs

and four thousand six hundred and forty seven only)

including five year Maintenance Cost

सहायक सलाहकार Superintending Engineer
ग्रामीण कार्य विभाग R.W.D. WORKS CIRCLE, PATNA
कार्य अंचल, पटना

21/02/21
Superintending Engineer
W.D. WORKS CIRCLE PATNA

RURAL WORKS DEPARTMENT

(Govt. of Bihar)

NAME OF ROAD : **EMERGENT REPAIR OF ROAD FROM Ghataurapur (PMGSY Road) To Daudpur UNDER FDR**

BLOCK **PANDARAK** DIV(RWD)-BARH

DISTRICT **PATNA** CIRCLE(RWD)-PATNA

Sl. No.	SDB SL.NO	MORD Ref.No	Item Description	Unit	Length	Width	Height	Quantity	Rate	Amount (in Rs.)
1			Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. QTY VIDE POT MEASUREMENT	Cum				185.20	2148.49	397921.93 397909.70

TOTAL= 397909.70

397921.93

BK
25/11/20
JE(RWD)

RLP
25/11/20
A E (RWD)

25/11/20
E E (RWD)
WORK DIVISION
BARH

Inspection Report for Flood Damage Work


Date: 26.12.2020

1. Name of PIU:- EE/RWD/Barh
2. Name of Block/Road:- Pandarna/ Ghatwarpar PMSY Rd. to Dandpur
- ✓ 3. For Road:-
4. Damage Location/Chainage:-
5. Damage Length:- 0.740 km
6. Nature of Damage:- A large no. of depressions/pot holes due to heavy rainfall
- I. Material being used in Restoration Works:- GSB gr. I
- II. Equipments/Tools being used in Restoration Works:- Tractor, water tanker, grader, Roller
- III. Procedure taken up in Restoration Works:- Laying, spreading & compacting GSB I
- IV. Restored Length:- 0.740 km

B. For Bridge

1. Damage Location/Chainage:-
2. Damage Length:-
3. Nature of Damage:-
4. Details of Restoration Works:-
- I. Material being used in Restoration Works:-
- II. Equipments/Tools being used in Restoration Works:-
- III. Procedure taken up in Restoration Works:-
- IV. Restored Length

N/A


Name of Inspector
Executive Engineer Patna
R.W.D, Works Division