



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T01 TO BIRANABARI

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 1533		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		1.533	KM
TOTAL COST OF F.D.R. PART - A		Rs. 5.960	Lacs
ADD G.S.T @ 12%		Rs. 0.715	Lacs
Add Seigniorage Fee @ 10 %		Rs. 0.406	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 7.081	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E.E. RWD (Works) Division Kishanganj-2


2. Name of Block/Road- Thakurganj / T01 to Birmabari


A. For Road

1. Damage Location/Chainage : 850m & 1100m /
2. Damage Length : 29.1
3. Nature of Damage : Flood damage ditch & flank cutting
4. Details of Restoration :
i Material being used in Restoration : Bricks Bats
ii Equipment/Tools being used in Restoration works: Tractor
iii Procedure taken up in Restoration works :
iv Restored Length : 29.1

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works :
iii Procedure taken up in Restoration works :
iv Restored Length :


Signature of JE/AE/EE


11/12/2020
AE


Signature
(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From Toi to Bisanbari.....

Head - FDR

Estimated cost - 07.081 Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.


Sanction of estimate is much needed for payment of the work which was already done.


11/12/20

J.E

R.W.D

Kishanganj-2


11/12/20

A.E

R.W.D

Kishanganj-2


12/12/20

E.E

R.W.D

Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 TO BIRANABARI
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 1.533

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	5.960
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
	TOTAL COST OF PROJECT =	5.960
	Add G.S.T. @ 12%	0.715
	Add Seigniorage Fee @ 10 %	0.406
	Total Cost of Restoration Work =	7.081

[Signature]
JE
RWD

[Signature]
11/12/20
AE
RWD

[Signature]
20/12/20
EE
RWD

Technically Approved for Rs. 7.081 Lacs (Seven Lacs eight thousand one hundred) only.

[Signature]
20/12/20
अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किरानगंज