



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L056 TO AAMBARI

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 1793		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		1.793	KM
TOTAL COST OF F.D.R. PART - A		Rs. 7.828	Lacs
ADD G.S.T @ 12%		Rs. 0.939	Lacs
Add Seigniorage Fee @ 10 %		Rs. 0.453	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 9.220	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date:

11.12.2020

1. Name of PIUs- Executive Engineer RWD, Works Division Kishanganj-2

2. Name of Block/Road- Dakurganj / L056 to Aambari.

A. For Road

1. Damage Location/Chainage : 210m

2. Damage Length : 24.8 m.

3. Nature of Damage : crust wastout and flexure cutting.

4. Details of Restoration :

i Material being used in Restoration

: Local Sand, Brick Bat

ii Equipment/Tools being used in Restoration works:

Tracker

iii Procedure taken up in Restoration works

:

iv Restored Length

: 24.8 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:


iii Procedure taken up in Restoration works

:


iv Restored Length

:

NA


Signature of JE/AE/EE


11/12/2020
AE


12/12/20


Signature

(Name of Inspector)

TECHINICAL REPORT

Name of Work - FDR To Road From Lase to Aambari

Head - FDR

Estimated cost - 09.220 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Amrta
11/12/20
J.E
R.W.D
Kishanganj-2

Amrta
11/12/20
A.E
R.W.D
Kishanganj-2

Amrta
11/12/20
E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L056 TO AAMBARI
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 1.793

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND FILLING	1.181
2	BRICK BAT	6.647
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		7.828
Add G.S.T. @ 12%		0.939
Add Seigniorage Fee @ 10 %		0.453
Total Cost of Restoration Work =		9.220

Ammon.
10/12/20
JE
RWD

Jeel
11/12/2020
AE
RWD

Jeel
11/12/2020
EE
RWD

Technically Approved For Rs. 9.220 Lacs (Nine Lacs twenty two thousand) only.

Jeel
20/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज