



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T02 PAWAKHALI RASIYA TO AADIWAI TOLA VIA
JOGIMOHAN

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 6500	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	6.500	KM
TOTAL COST OF F.D.R. PART - A	Rs. 10.244	Lacs
ADD G.S.T @ 12%	Rs. 1.229	Lacs
Add Seigniorage Fee @ 10 %	Rs. 0.440	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 11.914	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12.02.2020

1. Name of PIUs- E.E. RWD(W) Division, Kishanganj-2

2. Name of Block/Road- Thakurganj/ T02 Pansakhali Rasiya to Aadiwai
Tola Via Jogimohan.

A. For Road

1. Damage Location/Chainage : 4095M

2. Damage Length : 38M

3. Nature of Damage : Culvert Approach Washed out

4. Details of Restoration :

i Material being used in Restoration : Local sand, Botlebacks, bamboo.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length : 38.20M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :


iv Restored Length :

N.A.


Signature of JE/AE/EE


12/12/2020
AE


12/12/2020


Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... To 2 Pawakhali Rasiya to Adinwal
Tola via Jogamohan.

Head - FDR

Estimated cost - 11.214 Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Amyr
11/12/20
J.E
R.W.D
Kishanganj-2

Auf
11/12/20
A.E
R.W.D
Kishanganj-2

B
11/12/20
E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T02 PAWAKHALI RASIYA TO AADIWAI TOLA VIA JOGIMOHAN
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 6.500

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	5.512
2	BRICK BAT	4.628
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.105
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		10.244
Add G.S.T. @ 12%		1.229
Add Seigniorage Fee @ 10 %		0.440
Total Cost of Restoration Work =		11.914

[Signature]
12/12/20
JE
RWD

[Signature]
12/12/20
AE
RWD

[Signature]
21/12/20
EE
RWD

Technically Approved For Rs. 11.914 Laes (Eleven
Lae Ninety one thousand four hundred) only.

[Signature]
20/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज