


RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name of the Road :- ANDHARA PWD ROAD TO
ANDHARA VILLAGE

BLOCK : PARSAUNI

FDR

Rs. 172243.00

Year - 2019-20

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, BELSAND

प्रतिवेदन

पथ का नाम:-..... पथ
संलग्न प्राक्कलन 2020 के जुलाई माह में परसौनी प्रखंड
में आई भीषण बाढ़ से क्षतिग्रस्त 310581 PWD पथ से 310581 गांव
..... पथ में बाढ़ से क्षतिग्रस्त मरमाति मद से यातायात चालू करने हेतु तैयार किया
गया है।

जिराकी प्राक्कलित राशि Rs. 1.72 Lacs (.....)
.....) है।

पथ के क्षतिग्रस्त भाग में आवश्यकता अनुसार Prick Bats, Rabbish भरकर यातायात चालू
करने का प्रबंधन किया गया है।

प्रारम्भिक वर्तमान अनुसूचित दर पर बनाया गया है।

Saqib

28.01.2021

सहायक अभियंता

ग्रामीण कार्यविभाग, बेलसंड

Samar

28.01.21

सहायक अभियंता

ग्रामीण कार्यविभाग, बेलसंड

28.01.21

कार्यपालक अभियंता

ग्रामीण कार्यविभाग, बेलसंड

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

me of Road : ANDHARA PWD ROAD TO ANDHARA VILLAGE
ngth of Road : 1.176 Km
ock : Parsauni
TRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Thousands)
1	Total Cost for Motorable Roads	152427.00
2	Labour cess @1%	1524.27
3	GST @12%	18291.24
	Total Cost of Road Repair	172242.51
	Say	172243.00

Sagunb
28-01-2021
JE

Skeema
28/01/21
AE

10/1/21
EE

Technically, approved for Rs 1.722 lac (Rs one lac seventy two thousand two hundred) only

10/1/21
S.E
RWD Sitamarhi

21/02/2021
24/02/2021
29/05/2021
24/06/2021

Schedule of Quantity

VILLAGE

Block Parsauni

No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
OF ITEMS					
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.				
	80% of Brick bat Qty.	88.03	Cum	1546.00	136097.47
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4	Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Bats Qty	22.01	Cum	742.00	16329.94

Total **152427.41**
Say **152427.00**

Sagib
28.01.2021
JE

Skeema
28/01/21
AE

28/1/21
EE

Details of Measurement of ditches filled by brick bats and rabbish

Sr. No.	DESCRIPTION	UNIT	NOS.	NOS.	LENGTH	BREATH	HEIGHT	QTY.	Remarks
	Andhara PWD road to Andhara Village								
	1st. Km	m ³	1	1	6.40	6.125	2.25	88.200	(5*2+2.25)/2
	2nd Km	m ³	1	1	16.00	1.95	0.7	21.840	
		m ³						110.040	

Sagib

28.01.2021

J.R

S. Kumar

28/01/21

AK

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग
कार्य प्रमंडल, शिवहर

सं. 214 अमरपुर
शिवहर

दिनांक- 12/02/2021

उपस्थित-

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल शिवहर।

सूचना में,

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सीतामढ़ी।

विषय:- कार्य प्रमंडल बेलसंड के अधीन वर्ष 2020 की भयंकर बाढ़ से क्षतिग्रस्त पथों में
यातायात के पुनर्स्थापन हेतु तैयार किए गए प्राक्कलन की जांच के संबंध में।

प्रमाण- भवदीय प्रमाण-900 दिनांक-12.09.2020

संदर्भ:-

उपरोक्त विषय पर प्रासंगिक पत्र में दिए गए निर्देश के अनुपालन में कार्य प्रमंडल
बेलसंड के अधीन वर्ष 2020 की भयंकर बाढ़ से क्षतिग्रस्त पथों में यातायात पुनर्स्थापन हेतु
तैयार किए गए कार्य का स्थल निरीक्षण किया गया। इस पत्र के साथ सलग्न सूची के 52 पथों पर
स्थल जाँचीपरान्त प्राक्कलन तकनीकी अनुमोदन हेतु समर्पित किया जा रहा है।

अनु-पथों की सूची (कुल 52 पथ) सलग्न।

विभागाध्यक्ष



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल शिवहर

ग्रामीण कार्य प्रमंडल बेलसंड के अन्तर्गत वर्ष-2020 के बाद से क्षतिग्रस्त पथों के प्राक्कलन की सूची।

Sl No	Division	Block	Name of Road	Total cost in Lakh
1	Belsand	Parsouni	Ramani Middle School To Harpur Middle School Road	12.453
2	Belsand	Parsouni	Kanhauli Gajpatti To Bhulli REO Road	3.284
3	Belsand	Parsouni	Andhara PWD Road To Andhara Road Road	1.908
4	Belsand	Parsouni	Benipur To Dhurwar Road	12.267
5	Belsand	Parsouni	Belsand To Pamara Road	10.093
6	Belsand	Parsouni	Sundergrama Village To Vidhata Village At Manusara River	1.927
7	Belsand	Parsouni	Madanpur School West To Madanpur School East Road	5.313
8	Belsand	Parsouni	Muroul To Mushahari Tola Road	6.101
9	Belsand	Parsouni	Riga Road To Parsurampur Uter Tola	3.319
10	Belsand	Parsouni	Sarkhauli PWD To Kanhauli Gajpatti Road	8.679
11	Belsand	Parsouni	Pasurampur To Dhanhara Road	3.005
			TOTAL	68.349

[Signature]
19.2.20