



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR 2020-21

Name of Division - R.W.D. (W) Division Dhaka
Block :- Ghorasahan
District :- East Champaran

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan Bakuliya Road Nahar Chowk to Kaswa Barwa to Vijayee Road. Paraniya, Ward No-01

Length -	K.M
----------	-----

ESTIMATED COST :- 2808600.00 Lakh

SUBMITTED BY:

EXECUTIVE ENGINEER,
RWD WORKS DIVISION, DHAKA

प्रखंड का नाम :- बोडो/पु.एन.

शीर्ष :- म म द स य

प्राक्कलित राशि :- 2808600

અનુરક્ષણ અવધિ :- ૩૬૩(૫૧)

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।

23/12/2020
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, २/५

Name of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan
Bakuliya Road Nahar Chowk to Kaswa-Barwa to Vijayee Road.
Particulars work No-01

Head - 2245

Length-

S/No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Labour for laying dry graded Jhama Khola or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E.A.	cum	As Per	Appendix 1			1207.89 1191.64	2147.41	2808576.06 25,58,939
2		Providing and Laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, Protection Works, backfilling, concrete and masonry	M	0	2.50M	0	0	0	4744.43	0.00
3		Sand filling with Approved Materials seposited at site from roadway cutting and excavation from drain and foundation of other strecture graded and compected as per Technical Specification	M3					0	400.59	0.00
TOTAL (in Re.)										2808576.06
Total Rs-										2808600.00

23/12/2020
Junior Engineer,
Rural Works Department,
Works Section, Ghorasahan

23/12/2020
Assistant Engineer,
Rural Works Department,
Works Sub Division, Ghorasahan

23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Ghorasahan

Port Facts T.A.I.T.S is accorded for Rs. 28,08,600 =
(.....crore Twenty Eight lacs Eight thousand
.....six hundred.....) only.

S.E. (R.W.D.)
works Circle
Motihari

19-3-21

Post Facto T/S is accorded for Rs. 25,58,900/-
(— crore Twenty Five Fifty Eight lacs — thousand — hundred — only.

S.E. (R.W.D.)
works Circle
Motihari

Dosi
19-3-21

Name of Work:-

Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan
Bakuliya Road Nahar Chowk to Kaswa Barwa to Vijayee Road.
Bakuliya Road Nahar Chowk to Kaswa Barwa to Vijayee Road.

Appendix - I

Measurement for surfacing the Breach with Brick Bats

Sl. No.	Chainage Km	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	0.000	15.000	3.400	0.500	25.500
2	0.100	10.000	3.600	0.400	14.400
3	0.120	7.000	3.200	0.500	11.200
4	0.300 to 0.550	250.000	$\frac{5.50+3.80}{2}$	$(0.800+0.400)/2$	$\frac{813.75}{-930.000}$
5	0.600	10.000	3.900	0.500	19.500
6	0.620	15.000	3.800	0.400	22.800
7	0.700	5.000	4.100	0.500	10.250
8	0.800	10.000	4.200	0.400	16.800
9	0.830	60.000	$\frac{6.20+4.10}{2}$	0.800	247.200
10	0.850	8.000	3.200	0.400	10.240
Total					1191.64

Junior Engineer
Rural Works Department,
Works Section, Dhaka
Shamsuddin

Assistant Engineer
Rural Works Department,
Works Sub Division, Dhaka
Shamsuddin

Executive Engineer,
Rural Works Department,
Works Division, Dhaka

Inspection Report for Flood Damage Works

Date :-

1. Name of PIUs - Executive Engineer, RWD, Ghazipur

2. Name of Block - Ghazipur

Name of Road - Ghazipur Bazar and Higher Chowk to Jangra
Barua to Vijaya Road.

(A) For Road

Damage Location/Chainage :-

Damage Length

Nature of Damage :-

Water logging

Details of Restoration Works:-

(i) Material being used in Restoration works:- Bricks Ball

(ii) Equipments/ Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:- Departmental.

(iv) Restored Length 390M

Signature of Inspecting Officer
(Executive Engineer)

R.W.D, W.D.

Scanned by 28/12/2024
EFWD
Removal