



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR 2020-21

Name of Division - R.W.D. (W) Division Dhaka
Block :- Ghorasahan
District :- East Champaran

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan Bakuliya Road Nahar Chowk to Kaswa-Barwa to Vijayee Road. Paraniya Ward No-01

Length -	K.M
----------	-----

ESTIMATED COST :- 2808600.00 Lakh

SUBMITTED BY:

EXECUTIVE ENGINEER,
RWD WORKS DIVISION, DHAKA

तकनीकी प्रतिवेदन

पथ का नाम :- ~~कोशीपुर~~ कोशीपुर पथ नं. १६१ मो. ४२५१-१२१ के निम्न पथ
पथीय नं. ०१-०१

प्रमंडल का नाम :- कोशीपुर


शीर्ष :- ११६५५


प्राक्कलित राशि :- २४०४६००/-


अनुरक्षण अवधि :- ३०३५५५

प्रस्तुत प्राक्कलन ~~कोशीपुर~~ कोशीपुर पथ नं. १६१ मो. ४२५१-१२१ के निम्न पथ पथीय नं. ०१-०१ में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथांशों यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ... २४०४६०० ... रु० है। प्रस्तुत प्राक्कलन सचिव, ग्रामीण कार्य विभाग, पटना के पत्रांक-२२५४ दिनांक-३०.०६.२०२० के निर्देशानुसार तैयार किया गया है पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथांशों में ~~कोशीपुर~~ से भरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा कोशीपुर


२३/१२/२०२०
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल कोशीपुर


२३/१२/२०२०
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, कोशीपुर

Name of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan
Bakuliya Road Nahar Chowk to Kaswa-Barwa-to-Vijayee-Road.

Parag's work No-01

Head - 2245

Length-

Sl. No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Labour for laying dry graded dhama Khwa or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light running etc. all complete as per approved design, specification and direction of E.L.	cum	As Per	Appendix I			1107.89 1191.64	2147.41	2808576.06 25,58,939
2		Providing and Laying reinforced cement concrete pipe NPT for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, Protection Works, backfilling, concrete and masonry	M	0	2.50M	0	0	0	4744.43	0.00
3		Sand filling with Approved Materials deposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted as per Technical Specification	M3					0	400.59	0.00
TOTAL (in Re.)										2808576.06
Total Rs-										2808600.00

25,58,900 = 0

23/12/2020
Junior Engineer,
Rural Works Department,
Works Section, Ghorasahan

23/12/2020
Assistant Engineer,
Rural Works Department,
Works Sub Division, Ghorasahan

23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Ghorasahan

But Rs. 28,08,600 = 0
(Twenty Eight Eight thousand
Six hundred) only.

S.E. (R.W.D.)
works Circle
Motihari

19-3-21

Post Facto / is accorded for Rs. 25,58,900 =

(.....) crore Twenty Five Fifty Eight
lacs thousand

(.....) Nine hundred (.....) only.

S.E. (R.W.D.)

works Circle

Motihari

Doni

19.3.21

1.3/03/2021

Name of Work:-

Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Ghorasahan

Bakuliya Road Nahar Chowk to Kaswa-Barwa to Vijayee Road:

Bakuliya Road No. 1 No. 01

Appendix - I

Measurement for surfacing the Breach with Brick Bats

Sl. No.	Chainage Km	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	0.000	15.000	3.400	0.500	25.500
2	0.100	10.000	3.600	0.400	14.400
3	0.120	7.000	3.200	0.500	11.200
4	0.300 to 0.550	250.000	$\frac{5.50+3.80}{2}$	$(0.800+0.400)/2$	$\frac{813.75}{-930.000}$
5	0.600	10.000	3.900	0.500	19.500
6	0.620	15.000	3.800	0.400	22.800
7	0.700	5.000	4.100	0.500	10.250
8	0.800	10.000	4.200	0.400	16.800
9	0.830	60.000	$\frac{6.20+4.10}{2}$	0.800	247.200
10	0.850	8.000	3.200	0.400	10.240
Total					1307.890 1191.64

Junior Engineer

Rural Works Department,

Works Section, Dhaka
Ghorasahan

Assistant Engineer

Rural Works Department,

Works Sub Division, Dhaka
Ghorasahan

Executive Engineer,

Rural Works Department,

Works Division, Dhaka

Inspection Report for Flood Damage Works

Date -

1 Name of PIUs - Executive Engineer, R.W.D., Dhule

2 Name of Block - Gherasohar

Name of Road - Gherasohar Nakuliga Road Major Check to Reserve
Parvati Road No-01

(A) For Road

Damage Location/Chainage :-

Damage Length

Nature of Damage - Water Logging

Details of Restoration Works:-

(a) Material being used in Restoration works:- Bricks Bch

(b) Equipments/ Tools being used in Restoration works:-

(c) Procedure taken up in Restoration works:- Departmental

(d) Restored Length 390M

Signature of Inspecting officer
(Executive Engineer)

R.W.D., W.D.

Scanned by 28/12/2020
EF RWD
RWD