

Inspection Report for Flood Damage Works

Date:

1. Name of PUU - Executive Engineer, RWD, Dhaka

2. Name of Block - Chiraiya

3. Name of Road - Motihazi Dhaka PWD road to Madhubani
(A) For Road

Damage Location/Chainage :-

4. Damage Length :- 15.0 m

5. Nature of Damage:- Breach water logging

Details of Restoration Works:-

(i) Material being used in Restoration works:- Brick bats & 1.0m dia H.P

(ii) Equipments/ Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:- Departmental

(iv) Restored Length: 15.0 m

Signature of Inspecting Officer
(Executive Engineer)

R.W.D, W.D.

Scanned by CamScanner



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR 2020-21

Name of Division - R.W.D. (W) Division Dhaka
Block :- Chiraiya
District :- East Champaran

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Motihari Dhaka PWD Road to Madhubani Road

Length - 4.560 K.M

ESTIMATED COST :- 550900.00 Lakh

SUBMITTED BY:

**EXECUTIVE ENGINEER,
RWD WORKS DIVISION, DHAKA**

तकनिकी प्रतिवेदन

पथ का नाम :- मौजिदारी ढाका PWD फय 25 मयुवनी

प्रखंड का नाम :- चिरगा


शीर्ष :- ^hPMGSY M/R 3054 (New Maintenance Policy)

प्राक्कलित राशि :- 5,50,900=00


अनुक्षण अवधि :- निर्माणार्थ

प्रस्तुत प्राक्कलन मौजिदारी ढाका PWD फय 25 मयुवनी में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथांशों यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ... 5,50,900=00रु0 है। प्रस्तुत प्राक्कलन सचिव, ग्रामीण कार्य विभाग, पटना के पत्रांक-2254 दिनांक-30.06.2020 के निर्देशानुसार तैयार किया गया है पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथांशों में Brick bats से भरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


23/12/2020
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा चिरगा


23/12/2020
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल चिरगा


23/12/2020
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, ढाका

Name of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Motihari
Dhaka PWD Road to Madhubani Road

Head - 2245 Length- 1.189 km

Sl No	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Labour for laying dry graded Dhama Khoa or stone filter under Brick Pitching or Boulder Pitching in slope or upon including light ramming etc. all complete as per approved design, specification and direction of E.I	cum	As Per	Appendix I			239.960 228.15	2147.41	515292.50 489931.59
2		Providing and Laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, Protection Works, backfilling, concrete and masonry	M	3	2.50M	0	0	7.5	4744.43	35583.23
3		Sand filling with Approved Materials seposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted as per Technical Specification	M3	0				0	400.59	0.00
TOTAL (in Re.)									550875.73	525514.59
Total Rs-									550900.00	

23/12/2020
Junior Engineer,
Rural Works Department,
Works Section, Dhaka
Chiraiya

23/12/2020
Assistant Engineer,
Rural Works Department,
Works Sub Division, Dhaka
Chiraiya

23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Dhaka
Soy 5,25,500/-

Est. Facts T.A.T.S is accorded for Rs. 5,25,500 = *5*
(.....crore.....Five.....Twenty Five
.....lacs.....thousand
.....Five.....hundred.....) only.

26/3/21
S.E. (R.W.D.)
works Circle
Motihari
26-3-21

Name of Work:-

Estimate for Emergent Repair of Road breaches (Damaged by Flood) for Motihari
Dhaka PWD Road to Madhubani Road

Appendix - I

Measurement for surfacing the Breach with Brick Bats

Sl. No.	Chainage Km	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	2.840	15.000	$\frac{3.000+7.500}{2}$	$\frac{3.500+3.20}{2}$	275.620 263.81
2	Deduction of H.P	$3 \times (1.23)2 \times 5$	2.500		-35.660
				Total	239.960

23/12/2020
Junior Engineer
Rural Works Department,
Works Section, Dhaka

Chiraiya

23/12/2020
Asistant Engineer
Rural Works Department,
Works Sub Division, Dhaka

Chiraiya

23/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Dhaka

228.15