

Inspection Report for Flood Damage Works

Date :-

1 Name of PIUs - Executive Engineer, R.W.D., Dhaka

2 Name of Block - Chiraiya

Name of Road - Chiraiya Chowk to Ahirauliya Road

(A) For Road

Damage Location/Chainage :- Details given below

Damage Length :- 57.0m

Nature of Damage:- Water logging

Details of Restoration Works:-

(i) Material being used in Restoration works:- Brick bats

(ii) Equipments/ Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:- Departmental

(iv) Restored Length: 57.0m (fifty seven)


Signature of Inspecting officer
(Executive Engineer)

R.W.D, W.D. Raxaul



Rural Works Department, Govt of Bihar

Head- FDR(2245)

YEAR - 2020 - 21

Name of Division - R.W.D. (W) Division **Dhaka**

Block :- **Chiraiya**

District :- **East Champaran**

Name of Road - Estimate for Emergent Repair of Road breaches (Damaged Flood) for **CHIRAIYA CHOWK TO AHIRALIYA**

Length - **1.50 km**

ESTIMATED COST :- **1,15,000.00**

SUBMITTED BY:

EXECUTIVE ENGINEER,
RWD WORKS DIVISION, **Dhaka**

तकनीकी प्रतिवेदन

पथ का नाम :- चिरैया चौक से आहरीलिया पथ

खंड का नाम :- चिरैया

शीर्ष :- M/R 3054

प्रकल्पित राशि :- 1.15 Lac

अनुसंधान अवधि :- अनुसंधान अवधि से बाहर

प्रस्तुत प्राक्कलन चिरैया चौक से आहरीलिया पथ में अतिवृष्टि

बाढ़ से क्षतिग्रस्त पथांशों यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ...
 ...रु० है। प्रस्तुत प्राक्कलन सचिव, ग्रामीण कार्य विभाग, पटना के पत्रांक-2254
 दिनांक-30.06.2020 के निर्देशानुसार तैयार किया गया है पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त
 पथांशों में Brick balls से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


 22/12/2020

कनीय अभियंता,
 ग्रामीण कार्य विभाग,
 कार्य प्रशाखा चिरैया


 22/12/2020

सहायक अभियंता,
 ग्रामीण कार्य विभाग,
 कार्य अवर प्रमंडल चिरैया


 22/12/2020

कार्यपालक अभियंता,
 ग्रामीण कार्य विभाग,
 कार्य प्रमंडल, दाक

Name of Work:- Estimate for Emergent Repair of Road breaches (Damaged by Flood) for

Head - 2245 Length- CHIRAIYA CHOWK TO AHIRAU LIYA

Sl. No.	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
	Labour for laying dry graded thama Khola or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I	cum	As Per	Appendix			63.300 50.18	2147.41	1,14,457.00 1,07,757.03
	Manufacture and Laying reinforced cement concrete pipe S.P. for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, Protection Works, backfilling, concrete and masonry	M	0	2.50M	0	0			
	Soil filling with Approved Materials deposited at site from roadway cutting and excavation from drain and foundation of other structure graded and compacted as per Technical Specification	M3	0						
TOTAL (in Re.)									1,14,457.00
Total Rs.									1,15,000.00

22/12/2020
Junior Engineer,
Rural Works Department,
Works Section, Chiraiya

22/12/2020
Assistant Engineer,
Rural Works Department,
Works Sub Division, Chiraiya

22/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Dhaka
1,07,757 = ~
say 1,07,800 = ~

Post Facto T.A.T/S is accorded for Rs. 1,07,800 = ~

(..... crore. One lacs Seven thousand

Eight hundred only.

26/03/2021
S.E. (R.W.D.)
works Circle
Molihari
26-3-21

Name of Work : - Estimate for Emergent Repair of Road breaches (Damaged by Flood) for

CHIRAIYA CHOWK TO AHIRALIYA

Appendix - 1

Measurement for surfacing the Breach with Brick Bats Filling


for surfacing the Breach with Brick Bats Filling					
Sl. No.	Chainage Km	Length (M)	Avg. Width In Meter	Avg. Depth In Meter	Quantity (Cum)
1	0.015	8.000	3.900	0.600 0.5	18.720 15.60
2	0.200	5.000	1.200	0.600	3.600
3	0.400	4.000	2.000	0.700	5.600
		5.000	2.000	0.600	6.000
		3.000	1.000	0.500	1.500
		3.000	1.000	0.450	1.350
		2.000	1.000	0.350	0.700
		6.000	1.100	0.500	3.300
4	500	7.000	1.100	0.400	3.080
5	700	9.000	1.500	0.500	6.750
		2.000	1.000	0.450	0.900
		3.000	1.000	0.600	1.800
		Total			53.300


22/12/2020

Junior Engineer,
Rural Works Department,
Works Section.....Chiraiya


22/12/2020

Assistant Engineer,
Rural Works Department,
Works Sub Division, Chiraiya


22/12/2020

Executive Engineer,
Rural Works Department,
Works Division,.....Dhau