

Inspection Report for Flood Damage Work

Date:-.....

1. Name of PIUs:- E.E RWD Anna

2. Name of Block:- Anna

3. Name of Road:- Babbly G. Highway CH 3.0/4

A. For Road

1. Damage Location/Chainage :- 3.0 km

2. Damage Length :- 241 m

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :- 241 m

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-


(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

} N/A



Signature of JE/AE/EE



Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- अरुणिका नदी निवासी से अरुणिका नदी तक 150 म - 3.00 म

कार्य का नाम :- FDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संततन प्राक्कलन 10.06.2020 को प्रखण्ड में आसी भीषण बाढ़ से क्षतिग्रस्त 21/9/20


में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 3385494 है।

उक्त पथ का निर्माण MR योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में है।


भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान

अनुसूचित दर के अनुरूप है।



कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, अरुणिका



सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, अरुणिका



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, अरुणिका

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Ban Bibhag to Mahisakol via Bansvari At Ch-3.00 km	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	904602.27
2	Supply and Carriage of brick bats	2091391.99
	SUB TOTAL COST =	2995994.26
	ADD GST @ 12% =	359519.31
	Add Labour cess @ 1% =	29959.94
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	3385474

[Signature]
J.E

[Signature]
J.E

[Signature]
E.E

S.E

T/A for Rs- 33,85,474.26 (Rupees Thirty Three Lacs Eighty Five Thousand Four Hundred Seventy Four Only.)

[Signature]
25/11/20

Bill of Quantity

NAME OF ROAD :- Ban Bibhag to Mahisakol via Bansvari At Ch-3.00 km

DISTRICT :- Araria

BLOCK :- Araria

Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	1443.00	626.89	904602.27
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	975.00	2,145.02	2091391.99
		A) SUB TOTAL =		2995994.26
		TOTAL COST =		2995994

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

NAME OF ROAD :-		Ban Bibhag to Mahisakol via Bansvari At Ch-3.00 km									
DISTRICT :-		Araria									
BLOCK :-		Araria									
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)		
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge										
		cum	1	130.00	6.00	1.85	1443.00				
		cum	0	0.00	8.50	1.50	0.00				
		cum	0	0.00	(8.00+5.50)/2	1.50	0.00				
		cum		total qty :-			1443.00	626.89	904602.27		
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.										
		cum	1	130.00	5.00	1.50	975.00				
		cum	0	60.00	4.50	1.80	0.00				
		cum	0	26.00	4.50	1.80	0.00				
		cum	0	25.00	4.50	2.15	0.00				

Inspection Report for Flood Damage Work

Date:- 21.9.2020

1. Name of PIUs:- EE RWD Araria

2. Name of Block:- Araria

3. Name of Road:- Araria Bazar to Mahisakand via Banskura CH 7.8 Km

A. For Road

1. Damage Location/Chainage :- 7.8 Km

2. Damage Length :- 154 m

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:- Local sand, 1/2 bag, 1/2 bag H.P. / 4.5 B

(ii.) Equipments/Tools being used in Restoration works:- Tractor, JCB, Pallet

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :- 154 m

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

N/A

Signature of JE/AE/EE
21/9/20

Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- मुररिजा का निम्न ले सहायक पथ CH T-5 14

कार्य का नाम :- FDR
में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संतन प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त उपरोक्त
पथ में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है


जिसकी प्राक्कलित लागत 5916814/- है।

उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Araria Ban Bhibhag to Mahlsakol Via Banswarl AT CH-7.8 km	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	1167030.96
2	Labour for cutting 62mm to 75mm dia bamboo	26430.30
3	Supplying of EC bag, of local sand	272624.56
4	Supply and Carriage of brick bats	3267665.92
5	Supply, laying and carriage of 1000 mm HPC	286913.60
6	Granular Sub-base	215453.32
	SUB TOTAL COST =	5236118.66
	ADD GST @12% =	628334.24
	Add Labour cess @ 1% =	52361.19
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	5916814

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

S.E

T/A for Rs - 59,16,814.00 (Rupees Fifty Nine Lacs Sixteen thousand eight Hundred fourteen Only.)

[Signature]
28/11/20

Bill of Quantity

NAME OF ROAD :- Araria Ban Bhibhag to Mahisakol Via Banswari AT CH-7.8 km

DISTRICT :- Araria

BLOCK :- Araria

SL. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	1861.62	626.89	1167030.96
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	526.50	50.20	26430.30
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	7147.06	38.15	272624.56
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	1523.38	2,145.02	3267665.92
5	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	60.00	4,781.89	286913.60
6	Granular Sub-base with Well Graded Material (Table 400.1)	64.13	3,359.90	215453.32
A) SUB TOTAL =				5236118.66
TOTAL COST =				5236119

[Signature]
21/9/20
J.E

[Signature]
21/9/20
A.E

[Signature]
21/9/20
E.E

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- Arora

3.Name of Road:- Arora Bakhly Kehikane 417-514

A. For Road

1.Damage Location/Chainage :- 7514

2.Damage Length :- 75m

3.Nature of Damage :- m2u

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:- Trencher) 34)

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

2/1

Rup
21.9.20

21.9.20

Signature of JE/AE/EE

Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- डार्लिंग नदी किनारे से क्षतिग्रस्त एन-75एम
कार्य का नाम :- PDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आरी भीषण बाढ़ से क्षतिग्रस्त 84रोड

59 में बाढ़ क्षतिग्रस्त गरमति मद से यातायात चालू करने हेतु तैयार किया गया है
जिसकी प्राक्कलित लागत 2271382 है।


उक्त पथ का निर्माण 852 योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में 81।

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


21.9.20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।


21.9.20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।


21.9.20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Araria Ban Bhibhag to Mahisakol Via Banswari AT CH-7.5 km	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	632610.37
2	Labour for cutting 62mm to 75mm dia bamboo	3514.00
3	Supplying of EC bag,of local sand	30291.62
4	Supply and Carriage of brick bats	1271928.30
5	Supply,laying and carriage of 1000 mm HPC	71728.40
	SUB TOTAL COST =	2010072.69
	ADD GST @12% =	241208.72
	Add Labour cess @ 1%=	20100.73
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	2271382

J.E *[Signature]*
21.9.20

A.E *[Signature]*
21/9/20

E.E *[Signature]*

S.E

T/A for Rs- 22,71,382/- (Rupees Twenty two Lacs Seventy One Thousand Three Hundred Eighty two Only.)

[Signature]
28/9/20

Bill of Quantity

NAME OF ROAD :-		Araria Ban Bhibhag to Mahisakol Via Banswari AT CH-7.5 km		
DISTRICT :-		Araria		
BLOCK :-		Araria		
SL No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	1009.13	626.89	632610.37
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	70.00	50.20	3514.00
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	794.12	38.15	30291.62
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	592.97	2,145.02	1271928.30
5	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	15.00	4,781.89	71728.40
		A) SUB TOTAL =		2010072.69
		TOTAL COST =		2010073

[Signature]
J.E

[Signature]
A.E 21/9/20

[Signature]
E.E