



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

HEAD-FDR 2020

STATE:-BIHAR

DISTRICT:-Darbhanga

CIRCLE:-Darbhanga

DIVISION:-Jhanjharpur

BLOCK:-Madhepur

NAME OF WORK:-

**Detail Estimate for Restoration under F.D.R 2020
for Bheja Mahpaliya Road to Lalwarahi**

TOTAL COST FOR MOTORABLE Rs. 22.706 Lacs 16.870 lacs

AA Copy

Submitted By:-
Executive Engineer
RWD(W) Division, Jhanjharpur

प्रतिवेदन

पथ का नाम :- Bheja Mahptia road to Lalwarahi

पथ की लंबाई :-

प्राक्कलित राशि :- 22.706 लाख

प्रमण्डल का नाम :- झांझारपुर

अंचल का नाम :- दरभंगा


योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक में Bheja Mahptia road to Lalwarahi पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक मु0अ0-4-मु0- विविध कार्य-23-40/2016, 2789 अनु0, दिनांक 21.08.2020 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े / मिट्टी / स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान किया गया है करते हुए कार्य सम्पन्न किया जा चुका है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचित दर पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता

Abstract of Cost

NAME OF SCHEME : FDR 2020
 NAME OF ROAD : Bheja Mahpolija Road to Lalwarahi
 DISTRICT : Darbhanga
 BLOCK : Madhepur
 DIVISION : Jhanjharpur
 LENGTH OF ROAD :

Sl. No.	DESCRIPTION	AMOUNT
	RESTORATION WORK	
	TOTAL COST OF WORK BRICK BATS (Total quantity 1024.250 m ³ @ RATE Rs 1867.76)	₹ 19,13,053.18
	ADD GST @ 12 %	₹ 2,29,566.38
	ADD LABOUR CESS @ 1 %	₹ 19,130.53
	ADD SEIGNIORANGE FEE ((Total quantity 1024.250 x Rs 1063.00) x 10%)	₹ 1,08,877.78
	TOTAL COST BRICK BATS	₹ 22,70,627.87

14213654=00
 170564=00
 14214=00
 80894=00

1706385.53
 204746.26
 17063.85
 9715.68
 20,75,331.00

Total Rs 16,87,037=00

20,75,331.00

[Signature]

JE
RWD

[Signature]

AE
RWD

[Signature]

EE
RWD

कार्यपालक अभियंता ग्रामीण कार्य विभाग कार्य प्रमाण दरमंजरा - 1
 के पत्रांक-886 दिनांक 15/4/21 के द्वारा समर्पित जॉय प्रतिवेदन
 के आधार पर Post-Feet T/A for Rs 20,25,331=00
 (Rs Twenty Lac twenty five thousands three hundred thirty one) only
 Post-Feet T/A for Rs 16,87,037=00 (Rupee Sixteen lac-
 eighty seven thousand thirty seven) only.

[Signature]

Superintending Engineer

R.W.D. (W) CIRCLE, DARBHANGA.

[Signature]
 06/05/21

Detailed Estimate of Flood Damaged Road

Block:- Madhepur
District:- Darbhanga

Name of Division:- Jhanjharpur
Name of Work:- Bheja Mahpolija Road to Lalwarahi
Name of Scheme:- FDR 2020
Length(in Km):-

Sl. No.		SOR Sl.No.	Items of Work					
		6.61 WRD BIHAR	Providing and laying of Bricks bats with carriage by tractor loading with front end loader with light ramming etc all complete job					
1					Details of Actual Measurement			Quantity(m ³)
			No.	Length(m)	Breadth(average)(m)	Depth(average)(m)		
			1	16.00	(6.0+8.0)/2	0.60	67.200	
			1	12.00	(5.0+8.0)/2	(0.75+1.20)/2	76.050	
			1	40.00	(10.0+6.0)/2	2.50	800.000	
			2	12.00	(1.5+3.0)/2	1.50	81.000	
			Total					1024.250

215.60
761.00 m³

01/3/21

Asstt. Engineer

Executive Engineer

30/8/21

Junior Engineer