



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

HEAD-FDR 2020

STATE:-BIHAR

DISTRICT:-Darbhanga

CIRCLE:-Darbhanga

DIVISION:-Jhanjharpur

BLOCK:-Madhepur

NAME OF WORK:-

Detail Estimate for Restoration under F.D.R 2020

for V6 Bhagwanpur se Mahabhasung Hasauli

V
Bhith

Mahasingh

TOTAL COST FOR MOTORABLE Rs. 2.248 Lacs

1.969 lacs

AA Copy

Submitted By:-
Executive Engineer
RWD(W) Division, Jhanjharpur

प्रतिवेदन

पथ का नाम :- Bhith Bhagwanpur To Mahasingh Hasauli

पथ की लंबाई :-

प्राक्कलित राशि :- 2.248 लाख

प्रमण्डल का नाम :- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक में Bhith Bhagwanpur to Mahasingh hasauli पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक मु0अ0-4-मु0- विविध कार्य-23-40/2016, 2789 अनु0, दिनांक 21.03.2020 के आदेश के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े / मिट्टी / स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान किया गया है ~~जहाँ हुए कार्य का सम्पादन किया जा चुका है~~

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचित दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है।

8/25/21

कनीय अभियंता

8/25/21

सहायक अभियंता

कार्यपालक अभियंता

Abstract of Cost

NAME OF SCHEME : **FDR 2020**
 NAME OF ROAD : **V6 Bhagwanpur se Mahabhasung Hasauli**
 DISTRICT : **Darbhanga**
 BLOCK : **Madhepur**
 DIVISION : **Jhanjharpur**
 LENGTH OF ROAD

Sl. No.	DESCRIPTION	AMOUNT
	RESTORATION WORK	
1	TOTAL COST OF WORK BRICK BAT5 (Total quantity 101.40 m ³ @ RATE Rs 1867.76)	₹ 1,89,390.86
	ADD GST @ 12 %	₹ 22,726.90
	ADD LABOUR CESS @ 1 %	₹ 1,893.91
	ADD SEIGNIORANGE FEE ((Total quantity 101.40 x Rs 1063.00) x 10%)	₹ 10,772.82
	TOTAL COST BRICK BAT5	₹ 2,24,790.50

165857.08
 19902.85
 1658.91
 9473.44
 196858.00

[Signature]
 JE
 RWD

[Signature]
 AE
 RWD

[Signature]
 EE
 RWD

₹ 1,96,858.00

कार्यपालक अभियन्ता-ग्रा० स० वि० कार्य प्रमंडल दरभंगा-1 का पत्रांक 286/2020 दिनांक- 15/4/21 के द्वारा जॉय प्रमिशन के आवार पर post fact OT.A. for Rs 1,96,858.00 (Rupees one lakh ninety six thousand eight hundred fifty eight only.)

[Signature]
 06.05.21
 Superintending Engineer
 R.W.D. (W) CIRCLE, DARBHANGA
 06/05/2021

Detailed Estimate of Flood Damaged Road

Name of Division:-
Name of Work:-
Name of Scheme:-
Length(in Km):-

Jhanjharpur
V6 Bhagwanpur se Mahabhasung Hasauli
FDR 2020

Block:- Madhepur
District:- Darbhanga

SI. No.	SOR SI.No.	Items of Work					
1	6.61 WRD BIHAR	Providing and laying of Bricks bats with carriage by tractor loading with front end loader with light ramming etc all complete job					
			Details of Actual Measurement				
No.	Length(m)	Breadth(average)(m)	Depth(average)(m)	Quantity(m ³)			
1	225.00	(4.0+6.0)/2	0.60	66.00	75.000	m ³	
1	5.00	4.00	0.60	12.000		m ³	
1	8.00	3.00	0.60	14.400		m ³	
			Total	101.400	88.80	m ³	

3/25/21
Junior Engineer

Junior Engineer

Asstt. Engineer

Executive Engineer

Detailed Estimate of Flood Damaged Road

Name of Division:-
Name of Work:-
Name of Scheme:-
Length(in Km):-

Jhanjharpur
V6 Bhagwanpur se Mahabhasung Hasauli
FDR 2020

Block:- Madhepur
District:- Darbhanga

Sl. No.	SOR Sl.No.	Items of Work	Details of Actual Measurement				Quantity(m ³)
1	6.61 WRD BIHAR	Providing and laying of Bricks bats with carriage by tractor loading with front end loader with light ramming etc all complete job	No.	Length(m)	Breadth(average)(m)	Depth(average)(m)	
		Chainage 500m	1	25.00-22.00	(4.0+6.0)/2	0.60	75.000 m ³
		Chainage 1600m	1	5.00	4.00	0.60	12.000 m ³
		Chainage 1950m	1	8.00	3.00	0.60	14.400 m ³
Total							101.400 m ³
							28.80

25/3/21
Junior Engineer

Asstt. Engineer

Executive Engineer