

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road:-Dhaka Ghorasahan Road me Bisrahiya to Pipra	Length- 1.20 Km
Estimated Cost- Rs.:- 1,12,900.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- दाका - पोशसहन रोड में निशानिर्माण के लिए

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 1.25 किमी


शीर्ष :- 3054

प्राक्कलित राशि :- ₹ 1,12,900.00


अनुरक्षण अवधि :- - - - -

प्रस्तुत प्राक्कलन दाका - पोशसहन रोड में निशानिर्माण में अतिवृष्टि/बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो0...1,12,900.00... रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1-9-2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, दाका

for Restoration work of Road from Dhaka Ghorasahan Road me Bisrahiya to
for the year 2020-21 in Dhaka Block.

Length:- 1.20 Km

Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
CH:-375M to 420M 45.00x1.25x0.300 = 16.875M ³				
CH:-490M to 500M 10.00x1.50x0.300 = 4.50M ³				
CH:-555M to 575M 20.00x1.50x0.300 = 9.00M ³				
CH:-580M to 590M 10.00x4.10x0.600 = 24.60M ³				
Total = 54.975M ³	M ³	54.975	2053.84	1,12,910.00
		Total	Rs.	1,12,910.00
			Say Rs.	1,12,900.00

[Signature]
1.9.2020
J.E.

[Signature]
07/09/2020
A.E.

[Signature]
07/09/2020
E.E.

Post Facto T.A./T.S is accorded for Rs. 1,12,900 = ~
(.....crore..... One lacs Twelve thousand
..... Nine hundred only.

[Signature]
S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Dhaka Ghorasahan Road me Bishrahiya to Pipra

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 85 M

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
(ii) Equipments Tools being used in restoration works:-
(iii) Procedure take up in restoration works:- Departmental
(iv) Restored Length:- 85 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul