

GOVERNMENT OF BIHAR

FDR (2020-21)



Name of Road:- Kundwa Chainpur to Pundeo ChowkTak	Length-1.00 Km
Estimated Cost- Rs.:- 5,30,700.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- कुण्डवा - चैनपुर से पुनदेन चौक तक,

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 1.00 कि०मी०


शीर्ष :-

प्राक्कलित राशि :- ₹ 5,39,700.00


अनुरक्षण अवधि :- 10/12

प्रस्तुत प्राक्कलन कुण्डवा - चैनपुर से पुनदेन चौक तक में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० ₹ 5,39,700.00 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से मरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका



07/09/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका


Estimate for Restoration work of Road from Kundwa Chainpur to Pundeo ChowkTak
for the year 2020-21 in Dhaka Block.

Length:- 1.00Km

S. N.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded Jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bats)				
	CH:-35M to 100M $65.00 \times 4.10 + 5.10/2 \times 0.400 + 1.00 + 0.400/3 = 179.40M^3$				
	CH:-190M to 200M. $10.00 \times 4.00 + 5.00/2 \times 0.600 + 0.750 + 0.600/3 = 29.25M^3$				
	CH:-310M to 320M $10.00 \times 4.10 + 5.00/2 \times 0.450 = 20.48M^3$				
	CH:-380M to 390M $10.00 \times 4.00 \times 0.450 = 18.00M$				
	Total = 247.13M ³	M ³	247.13	2147.40	5,30,687.00
				Rs.	5,30,687.00
				Say Rs.	5,30,700.00


1.5.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

Rs. 5,30,700/- is accorded for Rs. 5,30,700/-
(.....) crore. Five Thirty thousand
Seven hundred (.....) only


S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Kundwa ^{Chainpur} ~~Chainpur~~ to Pundeo chowck Tak

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 95 M

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental
- (iv) Restored Length:- 95 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul