

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Raksha Yadavpur, Bakhari	Length-2.560 Km
Estimated Cost- Rs.:-5,25,200.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- रक्षा - यादवपुर - बरसरी

प्रखंड का नाम :- ढाका


पथ की लम्बाई :- 2.560 कि०मी०


शीर्ष :- 3054


प्राक्कलित राशि :- रु - 5,25,200.00

अनुरक्षण अवधि :- निर्माणाधीन

प्रस्तुत प्राक्कलन रक्षा - यादवपुर - बरसरी - में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० रु. 5,25,200.00 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है। प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, ढाका।



07/09/2020
सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, ढाका



07/09/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, ढाका

estimate for Restoration work of Road from Raksha Yadavpur Bakhari for the year 20-21 in Dhaka Block.
length:-2.560 Km

SL N.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded Jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) <u>CH:- 810M to 850</u> $40.00 \times 4.50 + 5.50 / 2 \times 0.800 + 1.10 + 0.800 / 3 = 180M^3$ <u>CH:- 2310M to 2335M</u> $25.00 \times 4.50 + 5.50 / 2 \times 0.500 + 0.750 + 0.300 / 3 = 64.58M^3$ Total = 244.58M³	M ³	244.58	2147.40	5,25,211.00
			Total=	Rs.	5,25,211.00
				Say Rs.	5,25,200.00


1.9.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

Post Facto T.A./TS is accorded for Rs. 5,25,200.00
(.....crore.....Five.....lacs.....Twenty Five.....Thousands.....
.....Two.....hundred.....,000.....)


S.E. (R.W.D.)
works Circle
Molihari
29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Raksha. yadavpur. Bakharz

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 65 m
3. Name of Damage:- Road damaged due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bala
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental.
 - (iv) Restored Length:- 65 m


24/12/2020
Executive Engineer
R.W.D. (W) Div
Raxaul