

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Karmawa Barharwa	Length-2.640 Km
Estimated Cost- Rs.:- 6,00,100.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- करमवा - बड़हरन रोड

प्रखंड का नाम :- झुझार

पथ की लम्बाई :- 2.640 कि०मी०

शीर्ष :- 3054

प्राक्कलित राशि :- ₹. 6,00,100-00

अनुरक्षण अवधि :- - -

प्रस्तुत प्राक्कलन करमवा - बड़हरन रोड में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो० 6,00,100-00 रु० है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है, तथा आवश्यकता अनुसार पथ में हयूम पाईप का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनूसूचित दर के अनुरूप है।

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, ढाका।

सहाय अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, ढाका

कार्यपालक अभियंता

ग्रामीण कार्य विभाग


कार्य प्रमण्डल, ढाका


Estimate for Restoration work of Road from Karmawa Barharwa for the year 2020-21 in Dhaka Block.

Length:- 2.640 Km


SL N O.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) CH:- 1250M to 1290M $40.00+35.00/2 \times 4.50+6.00/2 \times 1.00+1.80+1.00/3 = 249.37M^3$ CH:- 1770M to 1800M $30.00 \times 4.00+4.50/2 \times 0.300 = 38.25M^3$ Less for H.P $1 \times 22/7+4 \times (1.23)2 \times 5.00$ $(-) 5.94 M^3$ Total= 281.68M ³	M ³	281.68	2053.84	5,78,526.00
2	Supplying Fitting and and fixing Hume pipe 1000mm dia Hume pipe all complete as per approved design specification and direction of E/I. 1Row x 2 Nos. x 2.50M = 5M	M	5	4324.13	21621.00
			Total=	Rs.	6,00,147.00
				Say Rs.	6,00,100.00


1.9.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

Rest Fwd T.A.T/S is accorded for Rs. 6,00,100/-
(.....) crore..... Six..... lacs..... thousand
(.....) hundred..... only.


S.E. (R.W.D.)
works Circle
Motihari
29-12-20


Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer, R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Karmawa - Barharwa

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 70 M
3. Name of Damage:- Road cutting due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental.
 - (iv) Restored Length:- 70 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul