

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Kushmahwa to Haruhani	Length-3.523 Km
Estimated Cost- Rs.:- 10,07,900.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- कुशामहना से हरहानी

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 3.523 कि.मी.


शीर्ष :- 3054.

प्राक्कलित राशि :- ₹. 10,07,900 = 100


अनुसंधान अवधि :- निर्माणाधीन

प्रस्तुत प्राक्कलन कुशामहना से हरहानी में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो0...10,07,900...0000 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है, तथा आवश्यकता अनुसार पथ में ह्यूम पाईप का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.5.2020
कनीय अभियंता

ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


27/09/2020
सहाय अभियंता

ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


27/09/2020
कार्यपालक अभियंता


ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका


Estimate for Restoration work of Road from Kushmahwa to Haruhani for the year 2020-21 in Dhaka Block.

Length:- 3.523 Km

SL N O.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) CH:- 1550M to 1568 M $18.00+17.00/2+4.00+6.50/2 \times 1.00+2.50+1.50/3 = 153.125M^3$ CH:- 1950M to 1972 M $22.00+20.00/2+4.00+6.00/2 \times 1.10+1.80+1.10/3 = 140.00M^3$ CH:- 2670M to 2730M $60.00M+55.00/2 \times 4.10+5.50/2 \times 0.50+1.10+0.500/3 = 193.00M^3$ 486.325M³ Less for H.P $1 \times 22/7 + 4 \times (1.23) \times 5.00$ (-) 5.94 M³ Total= 480.385M³	M ³	480.385	2053.84	986634.00
2	Supplying Fitting and and fixing Hume pipe 1000mm dia Hume pipe all complete as per approved design specification and direction of E/I. 1Row x 2 Nos. x 2.50M = 5M	M	5	4258.65	21293.00
			Total=	Rs.	10,07,927.00
				Say Rs.	10,07,900.00


T. 9. 2020
JE.


07/09/2020
AE.


07/09/2020
EE.

Post Facto T.A. is accorded for Rs. 10,07,900.00
(.....crore.....Ten.....lacs.....thousand
.....Nine.....hundred.....) only.


S.E. (R.W.D.)
works Circle
Motihari
29-12-20


Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Kushmahwa to Haruhani

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 100 m
3. Name of Damage:- Road cutting due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental.
 - (iv) Restored Length:- 100 m


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul