

# GOVERNMENT OF BIHAR

## FDR (2020-21)



# बिहार सरकार

Name of Road:- Jhauaram kundwa Chainpur Road Sishani Via Jetwaliya	Length-5.25 Km
Estimated Cost- Rs.:- 6,30,100.00	Block- Dhaka

Submitted By  
Executive Engineer  
R.W.D. (W) Division Dhaka

# F.D.R (2020-21)

## तकनीकी प्रतिवेदन

पथ का नाम :- श्री आशम कुण्डवा चैनपुर के धिसहनी ग्रामा जेटवर्किंग

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 8.25 कि.मी.

शीर्ष :- उ.क.प.

प्राक्कलित राशि :- ₹: 6,35,100/-


अनुरक्षण अवधि :-

प्रस्तुत प्राक्कलन श्री आशम कुण्डवा चैनपुर के धिसहनी में अतिवृष्टि/वाढ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि ₹0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्राक्धान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनूचित दर के अनुरूप है।

  
1.9.2020

कनीय अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रशाखा, दाका।

  
27/09/2020

सहाय अभियंता  
ग्रामीण कार्य विभाग  
कार्य अवर प्रमंडल, दाका


  
07/09/2020


कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमण्डल, दाका


**ESTIMATE FOR RESTORATION WORK OF ROAD FROM JHAUARAM KUNDWA CHAINPUR ROAD  
SISHANI VIA JETWALIYA FOR THE YEAR 2020-21 IN DHAKA BLOCK.**

**Length:- 5.25 Km**


SL N O.	Name of Item	Unit	Quantity M <sup>3</sup>	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) <u>CH:- 685M to 710M.</u> 25.00x4.10x0.450 = 46.13M <sup>3</sup> <u>CH:-1440M to 1455M.</u> 15.00x4.00+6.00/2x 1.25+2.00+1.250/3 = 112.50M <sup>3</sup> <u>CH:-2600M to 2660M.</u> 60.00x4.00+5.00/2x(0.450+0.60+0.450)/3 = <u>135.00M<sup>3</sup></u> Total = 293.63M <sup>3</sup>	M <sup>3</sup>	293.63	2053.84	6,03,069.00
			Total=	Rs.	6,03,069.00
				Say Rs.	<del>6,30,100.00</del> 6,03,100.00

  
1.9.2020  
JE.

  
07/09/2020  
AE.

  
07/09/2020  
EE.

*Post Facts*  
T.A./TS is accorded for Rs. 630,100.00  
(.....crore..... Six lacs..... Thirty thousand  
..... One hundred ..... ) only.

  
29/12/20  
S.E. (R.W.D.)  
works Circle  
Motihari  
29-12-20


## Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.<sup>n</sup> Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Jhauaram Kundwa Chainpur Road to Sishari  
vic. Jethwadiya.

### (A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 100 m
3. Name of Damage:- Road cutting due to Flood.
4. Details of Restoration Work:-
  - (i) Material being used in Restoration works:- Brick bats
  - (ii) Equipments Tools being used in restoration works:-
  - (iii) Procedure take up in restoration works:- Departmental
  - (iv) Restored Length:- 100 m

  
24/12/2020  
Executive Engineer  
R.W.D. (W) Div.<sup>n</sup>  
Raxaul