

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road:- Karmawa to Telhara Mahangua Road	Length-2.50 Km
Estimated Cost- Rs.:-5,91,200.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन


पथ का नाम :- कुरुमना से तेलहारा - महुआ रोड
प्रखंड का नाम :- दाका
पथ की लम्बाई :- 2.50 कि०मी०
शीर्ष :- 3054
प्राक्कलित राशि :- रु० 5.91,200000.
अनुरक्षण अवधि :- नाई निर्माणशील


प्रस्तुत प्राक्कलन कुरुमना से तेलहारा - महुआ रोड में अतिवृष्टि / वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो०.....5.91,200000 रु० है। प्रस्तुत प्राक्कलन, सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता

ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020
सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका

**Estimate for Restoration work of Road from Karmawa to Telhara Mahangua Road
for the year 2020-21 in Dhaka Block.**

Length:- 2.50 Km

SL No.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
	CH:-2.0M to 4.0M R.C.C Bridge Approach Cutting				
	2.00x3.00x4.00 = 24.00M ³				
	CH:-90M to 100M				
	10.00x2.00x0.300 = 6.00M ³				
	CH:-150M to 160M				
	10.00x4.00x0.450 = 18.00M ³				
	CH:-385M to 430M				
	45.00x4.10x0.400 = 73.80 ³				
	CH:-550M to 570M				
	20.00x4.00x0.450 = 36.00 ³				
	CH:-670M to 690M				
	20.00x4.00x0.450 = 36.00 ³				
	CH:-700M to 715M				
	15.00x3.00x0.450 = 20.25 ³				
	CH:-1310M to 1350M				
	40.00x4.10x0.450 = 73.80M ³	M ³	287.85	2053.84	5,91,198.00
	Total= 287.85M ³				
			Total=	Rs.	5,91,198.00
				Say Rs.	5,91,200.00

JE.

AE.

EE.

T.A/S is accorded for Rs. 5,91,200 = 5
(.....crore Five lacs Ninety one thousand
Two hundred) only.

S.E. (R.W.D.)
works Circle
Motihari

29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Karmawa to Telhara Mahangua Road.

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 162 M

3. Name of Damage:- Road damaged due to flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 162 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul