

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Bhandar PWD Road to Mahammadpur Jitkahi Road through Kabristan	Length- 3.05Km
Estimated Cost- Rs.:- 9,87,400.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन


पथ का नाम :- भंडार PWD रोड से मुहम्मदपुर भिरकाही रोड भागा जमिस्तान
प्रखंड का नाम :- दाका
पथ की लम्बाई :- 3.05 कि०मी०
शीर्ष :- 3054
प्राक्कलित राशि :- ₹. 987,400.00
अनुरक्षण अवधि :- - - -

प्रस्तुत प्राक्कलन ~~भंडार PWD रोड से मुहम्मदपुर भिरकाही रोड भागा जमिस्तान~~ में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो0...9,87,400.00 रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।

प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका



07/09/2020


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका

Rate for Restoration work of Road from Bhandar PWD Road to Mahammadpur
Road through Kabristan for the year 2020-21 in Dhaka Block.
Length:- 3.05 Km

Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
CH:- 1700M to 1810M 110.00x4.10+4.70/2x0.300+0.500+0.300/3 = 177.47M ³				
CH:- 1850M to 1900M 50.00x4.10x0.450 = 92.25M ³				
CH:- 2000M to 2060M 60.00x4.10+4.70/2x0.450 = 118.80M ³				
CH:- 2300M to 2350M 50.00x4.10x0.450 = 92.25M ³				
Total = 480.77M ³	M ³	480.77	2053.84	9,87,425.00
		Total	Rs.	9,87,425.00
			Say Rs.	9,87,400.00


1.9.2020
J.E.


07/09/2020
A.E.


07/09/2020
E.E.

Post Fwdto T.A./TS is accorded for Rs. 9,87,400.00
(.....crore.....Nine.....lacs.....Eighty Seven
.....Four hundred) only.


S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

note:-

1. Name of PIUs:- Executive Engineer, R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Bhandar PWD Road Mahammadpur Jitkahi
Road through Kabristan

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 270 M

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 270 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul