

GOVERNMENT OF BIHAR

FDR (2020-21)



Name of Road:- Barharwa Fatehmmahmad to Ansari Tola	Length- 1.370 Km
Estimated Cost- Rs.:- 7,24,800.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- क३हरवा फतेहमोहम्मद से अन्सारी शोला

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 1.376 कि०मी०


शीर्ष :- MMGSY.

प्राक्कलित राशि :- ₹ 7.24,800.00

अनुरक्षण अवधि :- अन्दर

प्रस्तुत प्राक्कलन क३हरवा फतेहपुर मोहम्मद से अन्सारी में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो०...₹ 7.24,800.00 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता

ग्रामीण कार्य विभाग


कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, दाका


07/09/2020

कार्यपालक अभियंता


ग्रामीण कार्य विभाग


कार्य प्रमण्डल, दाका

Estimate for Restoration work of Road from Barharwa Fatehmmahmad to Ansari Tola
for the year 2020-21 in Dhaka Block.
Length:- 1.370 Km


SL No.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded Jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) CH:-850M to 882M $(32.00+30.00)/2 \times (4.00+6.00)/2 \times 1.25+2.50+1.25/3 = 258.33M^3$ CH:-910M to 990M $80.00 \times 1.0+1.20/2 \times (0.80+1.00)/2 = 79.20M^3$ Total = 337.53M ³	M ³	337.53	2147.40	7,24,812.00
			Total	Rs.	7,24,812.00
				Say Rs.	7,24,800.00


1.9.2020
J.E.


07/09/2020
A.E.


07/09/2020
E.E.

Post Facto T.A./S is accorded for Rs. 7,24,800/-
(.....crore..Seven.....lacs..Twenty Four
Eight.....hundred.....) only.


28/12/20
S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Barharwa Fatehmohammad to Ansari Tola,

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 112 M

3. Name of Damage:- Road damaged due to Flood

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:- -
- (iii) Procedure take up in restoration works:- Departmental
- (iv) Restored Length:- 112 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul