

GOVERNMENT OF BIHAR
FDR (2020-21)



Name of Road:- Narkatiya At Mathiya Narkatiya Road to Malkauniya Dhobi Tola	Length-3.774 Km
Estimated Cost- Rs.:- 2,90,200.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- ~~मदिया - नरकटिया रोड से मलकोनिया खोली डोला~~

प्रखंड का नाम :- ~~दाका~~

पथ की लम्बाई :- 3.774 कि.मी.


शीर्ष :- M.L.G.S.Y.

प्राक्कलित राशि :- ₹. 2,90,200.00


अनुरक्षण अवधि :- ~~अन्दर~~

प्रस्तुत प्राक्कलन ~~मदिया - नरकटिया रोड से मलकोनिया खोली डोला~~ में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो0...~~2,90,200.00~~...~~2,90~~...~~2,90~~ रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


7.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका



07/09/2020


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका


imate for Restoration work of Road from Narkatiya At Mathiya Narkatiya Road to Malkauniya Dhobi Tola for the year 2020-21 in Dhaka Block.

Length:- 3.774Km

L	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bats) CH:-680M to 685M (R.C.C Approach Road) $2 \times 2.50 \times 1.00 + 3.00 / 2 \times 2.00 + 3.00 / 2 = 25.00M$ CH:-1480M to 1415M $15.00 \times 1.50 + 2.0 + 1.50 / 3 \times 1.50 + 2.90 / 2 = 55.00M$ CH:-14345M to 1443M $6.00 + 8.00 / 2 \times 4.00 + 6.00 \times 2 \times 1.50 = 52.50M$ Total = 132.50M³	M ³	132.50	2147.40	2,84,531.00
2	Supplying and placing of send begs..... specification and direction of E/I.	Nos	200	28.27	5654.00
				Rs.	2,90,185.00
				Say Rs.	2,90,200.00


1.9.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

Fact T.A.T.S is accorded for Rs. 2,90,200.00
 (.....crore.....Two.....lacs.....Ninety.....thousand
 '.....Two.....hundred.....) only.


28/12/20
S.E. (R.W.D.)
works Circle


29-12-20
Motihari


Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Narkatiya At Mathiya Narkatiya Road to Malkauniya Dhobi Tola

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 28 m
3. Name of Damage:- Road cutting due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental
 - (iv) Restored Length:- 28 m


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul