

GOVERNMENT OF BIHAR
FDR (2020-21)



Name of Road:- Pakhpakri Gurhenwa Road to Saratha Purvi	Length- 1.450Km
Estimated Cost- Rs.:- 6,61,300.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- पंचपकड़ी गुरहेनवा रोड से सरादा झील

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 1.450 कि०मी०

शीर्ष :- Mm 634

प्राक्कलित राशि :- ₹ 6,61,300.00


अनुरक्षण अवधि :- 3-अन्दर

प्रस्तुत प्राक्कलन पंचपकड़ी गुरहेनवा रोड से सरादा झील में अतिवृष्टि / बाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो०....₹.6,61,300.00 रु० है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / बाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका

Estimate for Restoration work of Road from Pakhpakri Gurhenwa Road to Saratha
for the year 2020-21 in Dhaka Block.

Length:- 1.450 Km

Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) CH:-10M to 60M (Approach Road of R.C.C Bridge) Both Side $2 \times 25.00 \times 1.00 + 3.00 / 2 \times 1.00 + 1.50 / 2 = 250.00 \text{M}^3$ CH:-1415M to 1445M $30.00 \times 4.00 + 5.00 / 2 \times 0.300 + 1.00 + 0.300 / 3 = 72.00 \text{M}^3$ Total = 322.00M ³	M ³	322.00	2053.84	6,61,336.00
		Total	Rs.	6,61,336.00
			Say Rs.	6,61,300.00


1.9.2020
J.E.


07/09/2020
A.E.


07/09/2020
E.E.

Post Auto T.A./S is accorded for Rs. 6,61,300.00
(.....crore Six lacs Sixty one thousand
Three hundred only.


S.E. (R.W.D.)
works Circle
Motihari
29-12-20

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Pachpakri Gurherwa Path to Saratha puri

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 80 M.

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental
- (iv) Restored Length:- 80 M


Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul